QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

EMPOLYEE TRAINEESHIP	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		40	40	EA	MANUFACTURED TERMINAL SECTION, FLARED	621.50	
		47	47	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	
		1	1	EA	ANCHOR FOR CABLE RAIL	621.65	EST.
		4	4	EA	GUARDRAIL APPROACH SECTION, GALVANIZED TYPE I	621.70	
		2	2	EA	GUARDRAIL APPROACH SECTION, GALVANIZED TYPE II	621.71	
		120	120	LF	ALUMINUM APPROACH RAILING	621.74	II
		170	170	EA	REPLACE GUARDRAIL POST ASSEMBLY	621.76	EST.
		1200	1200	EA	REPLACE GUARDRAIL BEAM UNIT	621.77	EST.
		2000	2000	LF	ADJUST HEIGHT OF GUARDRAIL	621.79	EST.
		7800	7800	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	77
		5000	5000	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
		3000	3000	HR	FLAGGERS	630.15	EST.
	1		1	LS	FIELD OFFICE, ENGINEERS	631.10	
	1		1	LS	TESTING EQUIPMENT, CONCRETE	631.16	
	1		1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	
	1		1	LU	FIELD OFFICE, TELEPHONE (N.A.B.I.)	631.25	
520			520	HR	EMPLOYEE TRAINEESHIP	634.10	
		1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	
		1	1	LS	TRAFFIC CONTROL	641.10	
		4	4	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	
		121,500	121,500	LF	DURABLE 6 INCH WHITE LINE, RECESSED POLYUREA	646.426	342
		96,000	96,000	LF	DURABLE 6 INCH YELLOW LINE, RECESSED POLYUREA	646.436	488
		3200	3200	LF	DURABLE 12 INCH WHITE LINE, RECESSED POLYUREA	646.466	78
		90	90	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	5
		39	39	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	
		243,000	243,000	LF	TEMPORARY 6 INCH WHITE LINE, PAINT	646.622	
		192,000	192,000	LF	TEMPORARY 6 INCH YELLOW LINE, PAINT	646.632	
		6400	6400	LF	TEMPORARY 12 INCH WHITE LINE, PAINT	646.662	
		180	180	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	
		78	78	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	
		17,300	17,300	EA	LINE STRIPING TARGETS	646.76	EST.
		300	300	LF	PAINTED CURB	646.81	5
		300	300	SY	GEOTEXTILE UNDER STONE FILL	649.31	20
		100	100	LB	SEED	651.15	EST.
		400	400	LB	FERTILIZER	651.18	EST.
		1	1	TON	AGRICULTURAL LIMESTONE	651.20	EST.
		50	50	CY	TOPSOIL	651.35	EST.
		2350	2350	SY	TEMPORARY EROSION MATTING	653.20	41

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

QUANTITY SHEET #2

PROJECT NAME: WINDSOR - HARTLAND

PROJECT NUMBER: IM 091-1(61)

FILE NAME: p07a142.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.L.
IPARM FILE: p07a142qs2.i

PLOT DATE: 16-AUG-2011 13:41
DRAWN BY: C.A.K.
CHECKED BY: R.A.B.
SHEET 7 OF 56