QUANTITY SHEET 3

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

EMPOLYEE TRAINEESHIP	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		787	787	SF	TRAFFIC SIGNS, TYPE A	675.20	0.50
		1213	1213	SF	TRAFFIC SIGNS, TYPE B	675.21	0.50
		5300	5300	LB	W-SHAPE STEEL SIGN POST	675.31	68.7
		7900	7900	LB	TUBULAR STEEL SIGN POST	675.33	179.5
		1200	1200	LF	SQUARE STEEL SIGN POST AND ANCHOR	675.341	122
		12	12	EA	FOUNDATION FOR W-SHAPE SIGN POST, 24 INCH DIAMETER	675.41	
		56	56	EA	FOUNDATION FOR TUBULAR STEEL POST	675.43	
		118	118	EA	REMOVING SIGNS (TYPE A)	675.50	
		9	9	EA	REMOVING SIGNS (TYPE B)	675.50	
		14	14	EA	ERECTING SALVAGED SIGNS	675.60	
		1200	1200	EA	DELINEATOR WITH STEEL POST	676.10	22
		1065	1065	EA	REMOVAL OF EXISTING DELINEATOR	676.12	
		1	1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	
		100	100	EA	SPECIAL PROVISION (CABLE GUARDRAIL J-BOLT, GALVANIZED)	900.620	EST.
		5	5	EA	SPECIAL PROVISION (CABLE GUARDRAIL SPLICE UNIT)	900.620	EST.
		500	500	EA	SPECIAL PROVISION (STEEL BEAM GUARDRAIL DELINEATOR)	900.620	EST.
		250	250	EA	SPECIAL PROVISION (STEEL BEAM GUARDRAIL OFFSET BLOCK)	900.620	EST.
		25	25	LF	SPECIAL PROVISION (REPLACEMENT OF GUARDRAIL CABLE)	900.640	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

QUANTITY SHEET #3

PROJECT NAME: WINDSOR - HARTLAND

PROJECT NUMBER: IM 091-1(61)

FILE NAME: p07a142.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.L.
IPARM FILE: p07a142qs3.i

PLOT DATE: 16-AUG-2011 13:41
DRAWN BY: C.A.K.
CHECKED BY: R.A.B.
SHEET 8 OF 56