STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 13

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
RAMP D: DI4+23.0, LT	WRONG WAY	1	36	24	6.00						1					X		X															SIGN ID CODE R5-1A SIGNS TO BE INSTALLED FACING OPPOSING TRAFFIC.		E-143
		1	24	24	4.00																											SIGN ID CODE R9-4A		E-143
DI5+72.0, RT	ONE WAY / ONE WAY	1 1	36 36	12 12	3.00 3.00						1					X		X															BACK-TO-BACK SIGN ID CODE R6-1R SIGN ID CODE R6-1L		E-142 E-142
	STOP / DO NOT ENTER	1 1	30 30	30 30	6.25 6.25																											BACK-TO-BACK SIGN ID CODE R1-1 SIGN ID CODE R15-1		E-143 E-143
DI5+72.0, LT	ONE WAY / ONE WAY	1 1	36 36	12 12	3.00 3.00						1					X		X															BACK-TO-BACK SIGN ID CODE R6-1R SIGN ID CODE R6-1L		E-142 E-142
	STOP / DO NOT ENTER	1 1	30 30	30 30	6.25 6.25																											BACK-TO-BACK SIGN ID CODE R1-1 SIGN ID CODE R5-1		E-143 E-143
	SUBTOTAL THIS SHEET				47.00	-	-								-	42	-						-	-	-		-	-		-					
	SHEET 19 SUBTOTAL SHEET 20 SUBTOTAL SHEET 21 SUBTOTAL				46.33 49.50 91.13	240.00 279.50 31.50	2 1 1								14 - -	84 84 42	- - 28						3 2 8	- 96.2 1044.5	- - -		963.6 - -	2 4 -		1037.4 1655.4 -					
	SHEET 22 SUBTOTAL SHEET 23 SUBTOTAL SHEET 24 SUBTOTAL				40.00 60.66 98.63	- - 22.50	3 2 -								- 14 -	140 112 42	28 - -						2 6 10	228.0 633.9 1255.1	- - -		- - -	- - -		- - -					
	SHEET 25 SUBTOTAL SHEET 26 SUBTOTAL SHEET 27 SUBTOTAL				54.00 46.00 33.00	135.50 443.50 -	2 - 3								- - -	112 28 140	- - -						2 5 2	228.0 - 300.5	- 283.5 -		- 973.8 -	2 4 -		831.3 1707.2 -					
	SHEET 28 SUBTOTAL SHEET 29 SUBTOTAL SHEET 30 SUBTOTAL				57.75 77.00 85.50	30.00 - 30.00	- - -								- - -	70 42 56	- - -						6 2 8	638.4 218.3 856.7	- - -		- - -	- - -		- - -					
	ROUNDING				0.50	0.50	-								7	106	9						-	100.4	16.5		62.6	-		68.7					
											LF	LF	LF		LF 35	LF 1100	LF 65		EA.	LB	LB	LB		LB 5600	LB 300	LB	LB 2000								
TOTALS					SF 787	SF 1213	EA. 14	SF			LF				LF 1200					LB			EA. 56	LB 7900				EA. 12	EA.	LB 5300					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #13

PROJECT NAME: WINDSOR - HARTLAND
PROJECT NUMBER: IM 091-1(61)

FILE NAME: p07a142.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.L.
IPARM FILE: p07a142tss13.i

PLOT DATE: 16-AUG-2011 13:42
DRAWN BY: C.A.K.
CHECKED BY: R.A.B.
SHEET 31 OF 56