STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #1

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																REMARKS	SIGN DETAIL	
		EA	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft			SQUARE STEEL (in) lb/ft			ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft			FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft				W-SHAPE STEEL FTG. SIZE		WEIGHT	POST SIZE	SIGN FRAME REQUIRED		DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												1.12	2.0	3.0	1.75	2.0	2.5			3.0	4.0	4.0 MOD		3.0	3.5	4.0	5.0	24"	30"						
															1.88	2.42	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6								
											OPTION ITEMS																									
INT. 17 RAMP A																																			
~~MM 0.090~~		1	36	36	9.00						1					X		X																W3-1A		E-150
~~MM 0.140~~	WRONG WAY	1	36	24	6.00						2					X		X																R5-1A		E-143
~~MM 0.190~~	STOP	1	30	30	6.25						1					X		X																R1-1		
NB MM 106.0	MILE 106	1	12	36	3.0						1					8.8' X		X																REPLACED DAMAGED MM 106 SIGN AND POST		E-143
INT. 17 RAMP B																																			
~~MM 0.040~~	YIELD	1	36	36	3.90						1					X		X																R1-2		E-146
SB MM 110.084							1				1					14.0' X		X																REPLACED A DAMAGED POST ON AN EXISTING SIGN		
INT. 17 RAMP C																																			
~~MM 0.150~~		1	36	36	9.00						1					X		X																W3-1A		E-150
~~MM 0.200~~	WRONG WAY	1	36	24	6.00						2					X		X																R5-1A		E-143
~~MM 0.254~~	STOP	1	30	30	6.25						1					X		X																R1-1		E-143
NB RAMP A MM 110.10							1			2													1										NEW FOUNDATION DUE TO RAMP WIDENING		
INT. 17 RAMP C																																			
~~MM 0.040~~	YIELD	1	36	36	3.90						1					X		X																R1-2		E-146
	SUBTOTAL				~~50.3~~		2									~~120~~								1												
	ROUNDING				~~4.7~~ 3.0											~~30~~																				
												FT	FT	FT	FT	FT ~~150~~ 22.8	FT		EA	LB	LB	LB		LB	LB	LB	LB								
	SHEET TOTAL	SF ~~55.0~~ 3	SF	EA. 2	SF							FT			FT ~~150~~ 22.8					LB			EA. 1	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #1

PROJECT NAME: NEWBURY
PROJECT NUMBER: IM 091-2 (77)

FILE NAME: p07a146.dgn
PROJECT LEADER: T. DOMEY
DESIGNED BY: JLR/LSW
IPARM FILE NAME: p07a146tssl.i

PLOT DATE: 25-OCT-2011 14:22
DRAWN BY: PM
CHECKED BY: PM
SHEET 19 OF 20