

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES					TOTALS	DESCRIPTIONS				
ROADWAY	EMPLOYEE TRAINEESHIP	BRIDGE	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUND	
1000					1000	HR	FLAGGERS	630.15	EST.	
				1	1	LS	FIELD OFFICE, ENGINEERS	631.10	-	
				1	1	LS	TESTING EQUIPMENT, CONCRETE	631.16	-	
				1	1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-	
				3000	3000	DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-	
	520				520	HR	EMPLOYEE TRAINEESHIP	634.10	-	
1					1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-	
1					1	LS	TRAFFIC CONTROL	641.10	-	
2					2	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-	
2200					2200	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	50	
96200					96200	LF	DURABLE 6 INCH WHITE LINE, RECESSED POLYUREA	646.426	943	
76000					76000	LF	DURABLE 6 INCH YELLOW LINE, RECESSED POLYUREA	646.436	730	
3980					3980	LF	DURABLE 12 INCH WHITE LINE, RECESSED POLYUREA	646.466	48	
85					85	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	5	
31					31	EACH	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-	
4350					4350	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	50	
192400					192400	LF	TEMPORARY 6 INCH WHITE LINE, PAINT	646.622	1887	
152000					152000	LF	TEMPORARY 6 INCH YELLOW LINE, PAINT	646.632	1459	
7900					7900	LF	TEMPORARY 12 INCH WHITE LINE, PAINT	646.662	36	
165					165	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	5	
20					20	EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-	
4600					4600	EACH	LINE STRIPING TARGETS	646.76	54	
			6770		6770	SY	GEOTEXTILE UNDER STONE FILL	649.31	70	
			150		150	LB	SEED	651.15	5	
			500		500	LB	FERTILIZER	651.18	EST.	
			2		2	TON	AGRICULTURAL LIMESTONE	651.20	EST.	
			2		2	TON	HAY MULCH	651.25	EST.	
			25		25	CY	TOPSOIL	651.35	EST.	
			5100		5100	SY	TEMPORARY EROSION MATTING	653.20	34	
65					65	EACH	DELINEATOR WITH STEEL POST	676.10	1	
65					65	EACH	REMOVAL OF EXISTING DELINEATOR	676.12	1	
1					1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-	
970					970	EA	SPECIAL PROVISION (CABLE GUARDRAIL J-BOLT, GALVANIZED)	900.620	EST.	
39					39	EA	SPECIAL PROVISION (CABLE GUARDRAIL SPLICE UNIT)	900.620	EST.	
34					34	EA	SPECIAL PROVISION (DECOMMISSION CURB DROP INLET)	900.620	EST.	
500					500	LF	SPECIAL PROVISION (REPLACEMENT OF GUARDRAIL CABLE)	900.640	EST.	

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS
		ITEM 649.31 GEOTEXTILE UNDER STONE FILL
4685	SY	DITCH CLEANING
2015	SY	SLOPE EROSION REPAIR
70	SY	ROUNDING
6770	SY	TOTAL
		ITEM 651.15 SEED
99	LB	NORTHBOUND DITCH CLEANING
46	LB	SOUTHBOUND DITCH CLEANING
5	LB	ROUNDING
150	LB	TOTAL
		ITEM 653.20 TEMPORARY EROSION MATTING
4466	SY	DITCH CLEANING
400	SY	SLOPE EROSION REPAIR
200	SY	SEED PROTECTION
34	SY	ROUNDING
5100	SY	TOTAL
		NOTE: ALL EXISTING CURB BOARD AND CURB DI'S WERE ELIMINATED ON THIS PROJECT WITH THE EXCEPTION OF ONE DI AND ONE SHORT SECTION OF CURB BOARD.
		ONE CURB DI REHABILITATED AT 163.162 RT AND ONE SECTION OF CURB BOARD RETAINED AT NB 163.163 - 163.221 RT

PROJECT NAME: IRASBURG - DERBY
PROJECT NUMBER: IM 091-3(47)
FILE NAME: p07a148.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p07a148qs02.i
PLOT DATE: 04-DEC-2012 13:4
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 7 OF 28