

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
								ROADWAY	EROSION CONTROL	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								1		1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	-			
								0.82		0.82		ACRE	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.11	-			
								1		1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-			
								40		40		HR	POWER BROOM RENTAL, TYPE II	608.31	EST.			
								2		2		EACH	ENERGY ABSORPTION ATTENUATOR	621.56	-			
								1520		1520		LF	REMOVE AND RESET GUARDRAIL	621.75	50			
								1650		1650		LF	TEMPORARY TRAFFIC BARRIER	621.90	50			
								560		560		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
								1		1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
								1		1		LS	MOBILIZATION/DEMobilIZATION	635.11	-			
								1		1		LS	TRAFFIC CONTROL	641.10	-			
								1		1		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
								1		1		EACH	PORTABLE ARROW BOARD	641.16	-			
								1650		1650		LF	TEMPORARY 6 INCH WHITE LINE, TYPE II TAPE	646.621	50			
								45		45		EACH	RAISED PAVEMENT MARKERS, TYPE I	646.80	-			
								450		450		SF	PAVEMENT MARKING MASK	646.86	50			
								35		35		SY	GEOTEXTILE FOR SILT FENCE	649.51	2			
								200		200		LB	SEED	651.15	6			
								820		820		LB	FERTILIZER	651.18	10			
								4		4		TON	AGRICULTURAL LIMESTONE	651.20	0.8			
								1		1		LS	EPSC PLAN	652.10	-			
								20		20		HR	MONITORING EPSC PLAN	652.20	EST.			
								1		1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	-			
								7900		7900		SY	TEMPORARY EROSION MATTING	653.20	57			
								120		120		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25	8			
								15		15		CY	VEHICLE TRACKING PAD	653.35	EST.			
								2		2		EACH	INLET PROTECTION DEVICE, TYPE I	653.40	-			
								1850		1850		LF	PROJECT DEMARCATION FENCE	653.55	21			
								1000		1000		CY	SPECIAL PROVISION (REMOVAL OF LEDGE SALVAGE MATERIAL)	900.608	-			
								200		200		HR	SPECIAL PROVISION (HAND SCALING)	900.630	EST.			
								1450		1450		LF	SPECIAL PROVISION (ROCKFALL BARRIER FENCE)	900.640	-			