

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
ROADWAY	EROSION CONTROL	FULL C. E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS						
1			1		ACRE	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.11	.008									
8747			8747		CY	COMMON EXCAVATION	203.15	-									
50			50		CY	SOLID ROCK EXCAVATION	203.16	EST									
25			25		CY	TRENCH EXCAVATION OF EARTH	204.20	7									
15			15		CY	TRENCH EXCAVATION OF ROCK	204.21	EST									
1			1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-									
15			15		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30	5									
20			20		LF	24" CPEP	601.0920	2									
3			3		EACH	24" CPEPES	601.7020	-									
3			3		EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	-									
3			3		EACH	CAST IRON COVER WITH FRAME	604.55	-									
40			40		HR	POWER BROOM RENTAL, TYPE II	606.31	EST									
3			3		EACH	YIELDING MARKER POSTS	619.17	-									
2			2		EACH	ENERGY ABSORPTION ATTENUATOR	621.56	-									
2200			2200		LF	TEMPORARY TRAFFIC BARRIER	621.90	4									
240			240		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST									
320			320		HR	FLAGGERS	630.15	EST									
		1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-									
		3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-									
1			1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-									
1			1		LS	TRAFFIC CONTROL	641.10	-									
2			2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-									
1			1		EACH	PORTABLE ARROW BOARD	641.16	-									
4600			4600		LF	TEMPORARY 6 INCH WHITE LINE, TYPE II TAPE	646.621	EST									
100			100		EACH	LINE STRIPING TARGETS	646.76	EST									
450			450		SF	PAVEMENT MARKING MASK	646.86	EST									
	120		120		SY	GEOTEXTILE FOR SILT FENCE	649.51	2									
	150		150		LB	SEED	651.15	15									
	1150		1150		LB	FERTILIZER	651.18	23									
	5		5		TON	AGRICULTURAL LIMESTONE	651.20	49									
	350		350		CY	TOPSOIL	651.35	11									
	1		1		LS	EPSC PLAN	652.10	-									
	20		20		HR	MONITORING EPSC PLAN	652.20	EST									
	1		1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	-									
	6100		6100		SY	TEMPORARY EROSION MATTING	653.20	91									
	30		30		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25	4									
	15		15		CY	VEHICLE TRACKING PAD	653.35	EST									
	3		3		EACH	INLET PROTECTION DEVICE, TYPE I	653.40	-									
	2310		2310		LF	PROJECT DEMARCATION FENCE	653.55	8									
	1		1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-									

△ REVISED ITEM QUANTITY - 7/8/10

PROJECT NAME: ROCKINGHAM
PROJECT NUMBER: IM 091-(57)

FILE NAME: 07a158/Design/d07a158frm.dgn PLOT DATE: 08-JUL-2010
PROJECT LEADER: K. ROBE DRAWN BY: P. PELOUIN
DESIGNED BY: P. PELOUIN CHECKED BY: S. MENARD
QUANTITY SHEET 1 SHEET 8 OF 78