

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES					TOTALS	DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY	EMPLOYEE TRAINEESHIP	BRIDGE	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUND	QUANTITIES	UNIT	ITEMS
1500					1500	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			ITEM 649.31 GEOTEXTILE UNDER STONE FILL
1000					1000	HR	FLAGGERS	630.15	EST.	141	SY	DITCH CLEANING
				1	1	LS	FIELD OFFICE, ENGINEERS	631.10	-	116.4	SY	SLOPE EROSION REPAIR
				1	1	LS	TESTING EQUIPMENT, CONCRETE	631.16	-	2.6	SY	ROUNDING
				1	1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-	260	SY	TOTAL
				3000	3000	DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			ITEM 651.15 SEED
	520				520	HR	EMPLOYEE TRAINEESHIP	634.10	-	17	LB	DITCH CLEANING
1					1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-	80	LB	EROSION CONTROL
1					1	LS	TRAFFIC CONTROL	641.10	-	3	LB	ROUNDING
2					2	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-	100	LB	TOTAL
99800					99800	LF	DURABLE 6 INCH WHITE LINE, RECESSED POLYUREA	646.426	959			ITEM 653.20 TEMPORARY EROSION MATTING
80000					80000	LF	DURABLE 6 INCH YELLOW LINE, RECESSED POLYUREA	646.436	827	1061	SY	DITCH CLEANING
2660					2660	LF	DURABLE 12 INCH WHITE LINE, RECESSED POLYUREA	646.466	29	625	SY	GUARDRAIL M.T.S.
34					34	EACH	DURABLE LETTER OR SYMBOL, POLYUREA	646.494	-	200	SY	SEED PROTECTION
199700					199700	LF	TEMPORARY 6 INCH WHITE LINE, PAINT	646.622	2018	14	SY	ROUNDING
159900					159900	LF	TEMPORARY 6 INCH YELLOW LINE, PAINT	646.632	1555	1900	SY	TOTAL
5300					5300	LF	TEMPORARY 12 INCH WHITE LINE, PAINT	646.662	38			
68					68	EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-			
6250					6250	EACH	LINE STRIPING TARGETS	646.76	55			
			260		260	SY	GEOTEXTILE UNDER STONE FILL	649.31	2.6			
			100		100	LB	SEED	651.15	3			
			500		500	LB	FERTILIZER	651.18	EST.			
			2		2	TON	AGRICULTURAL LIMESTONE	651.20	EST.			
			2		2	TON	HAY MULCH	651.25	EST.			
			25		25	CY	TOPSOIL	651.35	EST.			
			1900		1900	SY	TEMPORARY EROSION MATTING	653.20	14			
96					96	EACH	DELINEATOR WITH STEEL POST	676.10	1			
95					95	EACH	REMOVAL OF EXISTING DELINEATOR	676.12	2			
1					1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-			
1205					1205	EACH	SPECIAL PROVISION (CABLE GUARDRAIL J-BOLT, GALVANIZED)	900.620	EST.			
42					42	EACH	SPECIAL PROVISION (CABLE GUARDRAIL SPLICE UNIT)	900.620	EST.			
56					56	EACH	SPECIAL PROVISION (DECOMMISSION CURB DROP INLET)	900.620	EST.			
500					500	LF	SPECIAL PROVISION (REPLACEMENT OF GUARDRAIL CABLE)	900.640	EST.			
5					5	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE 1)	900.680	EST.			
2870					2870	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	24			

PROJECT NAME: BARTON - IRASBURG
PROJECT NUMBER: IM 091-3(48)

FILE NAME: p07a286.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p07a286qs02.i

PLOT DATE: 06-JUL-2011
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 7 OF 40