

ITEM DETAIL SUMMARY SHEET 2

LOCATION			MISCELLANEOUS													REMARKS				
BEGIN MILE MARKER	END MILE MARKER	POS.	616.47 BIT. CONC. CUTTERS & TRAFF. ISL. TON	619.17 YIELDING MARKER POSTS EA	649.31 GEOTEXTILE UNDER STONE FILL SY	653.20 TEMP. EROSION MATTING SY	676.10 DEL. W/STEEL POST TYPE I EA	676.12 REMOVAL OF EXIST. DELINEATOR EA	900.620 S.P. (DECOMM. CURB DI) EA											
NORTHBOUND																				
155.989	163.000			224																QUANTITIES FOR USE AS DIRECTED BY THE ENGINEER
156.074	156.188	RT						1	1	1										REPAIR CABLE GUARDRAIL AS DIRECTED BY ENGINEER. REMOVE TREATED TIMBER CURB MM 156.074 TO 156.108
156.320	156.386	LT				25		1	1											INSTALL MTS FLARED MM 156.320 TO 156.327
156.329	156.383	RT				25		1	1											INSTALL MTS FLARED MM 156.329 TO 156.336
156.588	157.113	RT				25		1												INSTALL MTS FLARED MM 156.588 TO 156.595
157.066	157.134	LT				25														INSTALL MTS FLARED MM 157.066 TO 157.073
157.141		RT			7.2															REPAIR SLOPE EROSION
157.204	157.353	RT						1	1											REPAIR CABLE GUARDRAIL AS DIRECTED BY ENGINEER
157.636	157.759	RT						2	2	2										REPAIR CABLE GUARDRAIL AS DIRECTED BY ENGINEER. REMOVE TREATED TIMBER CURB MM 157.641 TO 157.751
157.901	158.017	LT						2	2											REPAIR CABLE GUARDRAIL AS DIRECTED BY ENGINEER
157.911	158.036	RT						2	2	1										REPAIR CABLE GUARDRAIL AS DIRECTED BY ENGINEER. REMOVE TREATED TIMBER CURB MM 157.967 TO 158.028
158.061	158.179	RT						2	2	2										INSTALL MTS FLARED MM 158.061 TO 158.068; INSTALL ANCHOR AT MM 158.176. REMOVE TREATED TIMBER MM 158.094 TO 158.172
158.217	158.310	LT						2	2											REPAIR CABLE GUARDRAIL AS DIRECTED BY ENGINEER
158.234	158.342	RT						2	2	1										REPAIR CABLE GUARDRAIL AS DIRECTED BY ENGINEER. REMOVE TREATED TIMBER CURB MM 158.304 TO 158.334
158.416	158.540	LT				25		2	2											INSTALL MTS FLARED MM 158.416 TO 158.423; INSTALL ANCHOR AT MM 158.537
158.466	158.603	RT				25		2	1	1										INSTALL MTS FLARED MM 158.466 TO 158.473; INSTALL ANCHOR AT MM 158.601. REMOVE TREATED TIMBER CURB MM 158.563 TO 158.596
158.631	158.723	RT				25		2	2	1										INSTALL MTS FLARED MM 158.639 TO 158.646; INSTALL ANCHOR AT MM 158.721. REMOVE TREATED TIMBER CURB MM 158.672 TO 158.716
158.635	158.700	LT				25		2	2											INSTALL MTS FLARED MM 158.635 TO 158.642; INSTALL ANCHOR AT MM 158.699
158.786	158.887	LT						2	2											REPAIR CABLE GUARDRAIL AS DIRECTED BY ENGINEER
158.900	158.019	RT				25		2	2	3										INSTALL MTS FLARED MM 158.900 TO 158.907; INSTALL ANCHOR AT MM 159.106. REMOVE TREATED TIMBER CURB MM 158.935 TO 159.014
159.174	159.484	RT						2	2	10										REPAIR CABLE GUARDRAIL AS DIRECTED BY ENGINEER. REMOVE TREATED TIMBER CURB MM 159.203 TO 159.445
159.192	159.269	LT						2	2											REPAIR CABLE GUARDRAIL AS DIRECTED BY ENGINEER
159.267	159.270	RT			16															REPAIR SLOPE EROSION
159.370	159.452	LT						2	2	1										REPAIR CABLE GUARDRAIL AS DIRECTED BY ENGINEER. REMOVE TREATED TIMBER CURB MM 159.392 TO 159.445
159.633	159.687	LT																		REPAIR CABLE GUARDRAIL AS DIRECTED BY ENGINEER. REMOVE TREATED TIMBER CURB MM 159.613 TO 159.665
159.646	159.790	RT				25		1	1											INSTALL MTS FLARED MM 159.644 TO 159.651
159.733	159.799	LT				25		1	1											INSTALL MTS FLARED MM 159.733 TO 159.740
159.853	160.448	RT						1	1	5										INSTALL ANCHOR AT MM 160.445. REMOVE TREATED TIMBER CURB MM 160.237 TO 160.443
SHEET SUBTOTALS:			-	224	23.2	275	38	36	28											

ITEM DETAIL SUMMARY SHEET #2	PROJECT NAME: BARTON - IRASBURG
	PROJECT NUMBER: IM 091-3(48)
	FILE NAME: p07a286.dgn
PROJECT LEADER: JLL	PLOT DATE: 06-JUL-2011
DESIGNED BY: STANTEC	DRAWN BY: STANTEC
IPARM FILE: p07a286ids02.i	CHECKED BY:
	SHEET 9 OF 40