

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						EROSION CONTROL	ROADWAY	BRIDGE I-89 BR. NO. 59-4S	BRIDGE I-89 BR. NO. 59-2	FULL C.E.	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
									180		180		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
									25		25		CY	GRANULAR BORROW	203.32				
							1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
									75		75		CY	STRUCTURE EXCAVATION	204.25				
									85		85		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
									22		22		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34				
									3010		3010		LB	REINFORCING STEEL	507.15				
									3		3		GAL	WATER REPELLENT, SILANE	514.10				
									12		12		CY	REMOVAL OF CONCRETE OR MASONRY	529.25				
								5	5		10		CY	CONCRETE, CLASS D	541.31				
							24				24		HR	POWER BROOM RENTAL, TYPE II	608.31				
								10	125		135		CY	STONE FILL, TYPE II	613.11				
									130		130		CY	STONE FILL, TYPE IV	613.13				
							100				100		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
								80			80		HR	FLAGGERS	630.15				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
							1				1		LS	MOBILIZATION/DEMobilIZATION	635.11				
									1		1		LS	TRAFFIC CONTROL (I89 - BR. NO. 59-2)	641.10				
								1			1		LS	TRAFFIC CONTROL (I89 - BR. NO. 59-4S)	641.10				
							2				2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
							2				2		EACH	PORTABLE ARROW BOARD	641.16				
									150		150		SY	GEOTEXTILE UNDER STONE FILL	649.31				
						280					280		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
						120					120		LB	SEED	651.15				
						500					500		LB	FERTILIZER	651.18				
						2					2		TON	AGRICULTURAL LIMESTONE	651.20				
						2					2		TON	HAY MULCH	651.25				
						270					270		CY	TOPSOIL	651.35				
						125					125		SY	GRUBBING MATERIAL	651.40				
						1					1		LS	EPSC PLAN	652.10				
						40					40		HR	MONITORING EPSC PLAN	652.20				
						1					1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
						5350					5350		SY	TEMPORARY EROSION MATTING	653.20				
						100					100		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
						30					30		CY	VEHICLE TRACKING PAD	653.35				
						2					2		EACH	FILTER BAG	653.45				
						1000					1000		LF	BARRIER FENCE	653.50				
								5	5		10		CY	SPECIAL PROVISION (CONTROLLED DENSITY (FLOWABLE) FILL)	900.608				
									313		313		LF	SPECIAL PROVISION (ALUMNUM PIPE LNER)(66") (EXISTING 84" PIPE)	900.640				

PROJECT NAME: RICHMOND - WILLISTON  
 PROJECT NUMBER: IM CULV(16)  
 FILE NAME: ...04-quantity sheet.dgn PLOT DATE: 3/15/2010  
 PROJECT LEADER: G. BOGUE DRAWN BY: E. ALLING  
 DESIGNED BY: M. CHENETTE CHECKED BY: G. BOGUE  
**QUANTITY SHEET 1** SHEET 4 OF 18

