QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
							BEGIN ALTERNATE A		
			17200		17200	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	181
			75		75	CWT	EMULSIFIED ASPHALT	404.65	EST
			1		1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
			1		1	LS	TRAFFIC CONTROL	641.10	-
			69200		69200	LF	TEMPORARY 6 INCH WHITE LINE	646.620	748
			56200		56200	LF	TEMPORARY 6 INCH YELLOW LINE	646.630	573
			1225		1225	LF	TEMPORARY 12 INCH WHITE LINE	646.660	25
			25		25	LF	TEMPORARY 24 INCH STOP BAR	646.680	4
			40		40	EA	TEMPORARY LETTER OR SYMBOL	646.690	-
			1		1	LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.)	900.650	-
			172500		172500	SY	SPECIAL PROVISION (PAVER PLACED SURFACE	900.675	1846
							TREATMENT, TYPE C)		
			500		500	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE	900.680	EST
							PAVEMENT, SMALL QUANTITY)		
							END ALTERNATE A		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		ALTERNATE A
		COLD PLANING, BITUMINOUS PAVEMENT
150	SY	BEGIN PROJECT
150	SY	END PROJECT
781	SY	BRIDGE 34N
781	SY	BRIDGE 35N
1013	SY	BRIDGE 36N
278	SY	U-TURN 39.460 LT
278	SY	U-TURN 41.935 LT
278	SY	U-TURN 46.385 LT
278	SY	EMERGENCY ACCESS 39.460 RT
1867	SY	EXIT 5 OFF RAMP A
133	SY	EXIT 5 END OFF RAMP A
133	SY	EXIT 5 END SM RAMP A
400	SY	EXIT 5 ON RAMP B
133	SY	EXIT 5 END ON RAMP B
133	SY	EXIT 5 END SM RAMP B
1867	SY	EXIT 6 OFF RAMP A
133	SY	EXIT 6 END OFF RAMP A
400	SY	EXIT 6 ON RAMP B
133	SY	EXIT 6 END ON RAMP B
7700	SY	SPOT REPAIR (ESTIMATED)
17019	SY	SUBTOTAL
181	SY	ROUNDING
17200	SY	TOTAL
		SPECIAL PROVISION (PAVER-PLACED SURFACE TREATMENT,
		TYPE C)
150021	SY	MAINLINE
278	SY	U-TURN 39.460 LT
278	SY	U-TURN 41.935 LT
278	SY	U-TURN 46.385 LT
278	SY	EMERGENCY ACCESS 39.460 RT
4667	SY	EXIT 5 RAMP A
320	SY	EXIT 5 SM RAMP A
1867	SY	EXIT 5 OFF RAMP
400	SY	EXIT 5 ON RAMP
240	SY	EXIT 5 SM RAMP B
2627	SY	EXIT 5 RAMP B
2893	SY	EXIT 6 OFF RAMP A
1867	SY	EXIT 6 OFF RAMP
400	SY	EXIT 6 ON RAMP
4240	SY	EXIT 6 ON RAMP B
170654	SY	SUBTOTAL
1846	SY	ROUNDING
172500	SY	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: BROOKFIELD-BERLIN
PROJECT NUMBER: IM SURF (11)

FILE NAME: ...08A152\...08A152.dgn
PROJECT LEADER: DOMEY
DESIGNED BY: HUNT
IPARM FILE NAME: 08A152_07.i

PLOT DATE: 31-OCT-2011
DRAWN BY: HUNT
CHECKED BY: PAVT MGMT
SHEET 7 OF 15