QUANTITY SHEET 3

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
							BEGIN ALTERNATE B		
			162,500		162,500	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	455.96
			545		545	CWT	EMULSIFIED ASPHALT	404.65	2.57
			14,350		14,350	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	171.15
			1		1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
			1		1	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-
			1		1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
			1		1	LS	TRAFFIC CONTROL	641.10	-
			69200		69200	LF	TEMPORARY 6 INCH WHITE LINE	646.620	748
			56200		56200	LF	TEMPORARY 6 INCH YELLOW LINE	646.630	573
			1225		1225	LF	TEMPORARY 12 INCH WHITE LINE	646.660	25
			25		25	LF	TEMPORARY 24 INCH STOP BAR	646.680	4
			40		40	EA	TEMPORARY LETTER OR SYMBOL	646.690	-
							END ALTERNATE B		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		ALTERNATE B
		COLD PLANING, BITUMINOUS PAVEMENT
147,057.37	SY	MAINLINE
14,986.67	SY	RAMPS
455.96	SY	ROUNDING
162,500	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
12,867.52	TON	MAINLINE
1,311.33	TON	RAMPS
171.15	TON	ROUNDING
14,350	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME:	BROOKFIELD-BERLIN
PROJECT NUMBER:	IM SURF (11)
FILE NAME: ...08A152\...08A152.dgn	PLOT DATE: 31-OCT-2011 15:27
PROJECT LEADER: DOMEY	DRAWN BY: HUNT
DESIGNED BY: HUNT	CHECKED BY: PAVT MGMT
IPARM FILE NAME: 08A152_07a.i	SHEET 8 OF 15