

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
			ROADWAY	EROSION CONTROL	189 - BR. NO. 9-1	189 - BR. NO. 9-2	189 - BR. NO. 20-4	189 - BR. NO. 29-1D	FULL C.E.	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
			1							1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
					35	30	35	35		135		CY	SOLID ROCK EXCAVATION	203.16				
					70	70	38	25		203		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
					60	60	60	60		240		CY	STRUCTURE EXCAVATION	204.25				
					45	45	45	45		180		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
					16	16	16	16		64		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34				
					2100	2100	2100	2100		8400		LB	REINFORCING STEEL	507.15				
					10	10	10	10		40		LF	DRILLING AND GROUTING DOWELS	507.16				
					1.5	1.5	1.5	1.5		6		GAL	WATER REPELLENT, SILANE	514.10				
					5	5	5	5		20		CY	CONCRETE, CLASS C	541.30				
					10	10	10	10		40		CY	CONCRETE, CLASS D	541.31				
			40							40		HR	POWER BROOM RENTAL, TYPE II	608.31				
								35		35		CY	STONE FILL, TYPE II	613.11				
					135	140	75			350		CY	STONE FILL, TYPE IV	613.13				
			160							160		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
									1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
			1							1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
			1							1		LS	TRAFFIC CONTROL (189 - BR. NO. 20-4)	641.10				
			1							1		LS	TRAFFIC CONTROL (189 - BR. NO. 29-1D)	641.10				
			1							1		LS	TRAFFIC CONTROL (189 - BR. NO. 9-1)	641.10				
			1							1		LS	TRAFFIC CONTROL (189 - BR. NO. 9-2)	641.10				
			2							2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
					105	105	55	35		300		SY	GEOTEXTILE UNDER STONE FILL	649.31				
				50						50		LB	SEED	651.15				
				330						330		LB	FERTILIZER	651.18				
				2						2		TON	AGRICULTURAL LIMESTONE	651.20				
				2						2		TON	HAY MULCH	651.25				
				180						180		CY	TOPSOIL	651.35				
					10	10	10	10		40		CY	SPECIAL PROVISION (CONTROLLED DENSITY (FLOWABLE) FILL)	900.608				
				40						40		HR	SPECIAL PROVISION (MONITORING EPSC PLAN)	900.630				
					470		390	140		1000		LF	SPECIAL PROVISION (ALUMINUM PIPE LINER)(60")(EXISTING 72" PIPE)	900.640				
						660				660		LF	SPECIAL PROVISION (ALUMINUM PIPE LINER)(60")(EXISTING 78" PIPE)	900.640				
					85	30	50	20		185		LF	SPECIAL PROVISION (TEST BORINGS)	900.640				
			1							1		LS	SPECIAL PROVISION (EPSC PLAN)	900.645				
							1			1		LS	SPECIAL PROVISION (TEMPORARY ACCESS ROAD AND STAGING AREAS, CULVERT)(189 - BR. NO. 20-4)	900.645				
								1		1		LS	SPECIAL PROVISION (TEMPORARY ACCESS ROAD AND STAGING AREAS, CULVERT)(189 - BR. NO. 29-1D)	900.645				
					1					1		LS	SPECIAL PROVISION (TEMPORARY ACCESS ROAD AND STAGING AREAS, CULVERT)(189 - BR. NO. 9-1)	900.645				
						1				1		LS	SPECIAL PROVISION (TEMPORARY ACCESS ROAD AND STAGING AREAS, CULVERT)(189 - BR. NO. 9-2)	900.645				

PROJECT NAME: HARTFORD - SHARON
PROJECT NUMBER: IM 089-1(55)
FILE NAME: z08a056qs.dgn PLOT DATE: 01/15/2009
PROJECT LEADER: E. P. DETRICK DRAWN BY: A. P. GUYETTE
DESIGNED BY: A. P. GUYETTE CHECKED: E. P. DETRICK
QUANTITY SHEET #1 SHEET 3 OF 20