QUANTITIES

QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

BRIDGE	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		10,000	10,000	LF	SHOULDER BERM REMOVAL	203.40	-
		3,850	3,850	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	44
		1	1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
		10,000	10,000	LB	BITUMINOUS CRACK SEALING, 'BLOW AND GO' METHOD	417.20	192
160			160	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	-
100			100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL W/ COARSSE AGGREGATE	580.20	-
		150	150	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.
		650	650	HR	UNIFORMED TRAFFIC OFFICERS	630.10	37
		1,250	1,250	HR	FLAGGERS	630.15	25
	1		1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-
		1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
		1	1	LS	TRAFFIC CONTROL	641.10	-
		6	6	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
		175,000	175,000	LF	6 '' WHITE LINE	646.214	1482
		131,000	131,000	LF	6 '' YELLOW LINE	646.215	1534
		10,000	10,000	LF	12 '' WHITE LINE	646.24	850
		16	16	LF	24 '' STOP BAR	646.26	-
		22	22	EA	LETTER OR SYMBOL	646.30	-
		89,510	89,510	LF	TEMPORARY 6 '' WHITE LINE	646.620	41
		67,710	67,710	LF	TEMPORARY 6 '' YELLOW LINE	646.630	267
		4,600	4,600	LF	TEMPORARY 12 '' WHITE LINE	646.660	25
		16	16	LF	TEMPORARY 24 '' STOP BAR	646.680	-
		22	22	EA	TEMPORARY LETTER OR SYMBOL	646.690	-
		4,900	4,900	EA	LINE STRIPING TARGETS	646.76	EST.
		25,300	25,300	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	EST.
		1	1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
		198,000	198,000	SY	SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)	900.675	369
		25	25	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE SURFACE PREPARATION, TYPE I)	900.680	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		SPECIAL PROVISION
		(PAVER-PLACED SURFACE TREATMENT, TYPE C)
97,009	SY	I-89 NB MM 91.875 ~ 98.005
97,009	SY	I-89 SB MM 91.875 ~ 98.005
3,133	SY	RAMP D (NORTHBOUND OFF-EXIT 17)
480	SY	RAMP E (NORTHBOUND OFF-EXIT 17)
197,631	SY	SUBTOTAL
369	SY	ROUNDING
198,000	SY	TOTAL
		COLD PLANING, BITUMINOUS PAVEMENT
211	SY	BEGIN PROJECT APPROACH NORTHBOUND
211	SY	BEGIN PROJECT APPROACH SOUTHBOUND
211	SY	END PROJECT APPROACH NORTHBOUND
211	SY	END PROJECT APPROACH SOUTHBOUND
700	SY	BRIDGE 76 NORTHBOUND
700	SY	BRIDGE 76 SOUTHBOUND
781	SY	BRIDGE 77 NORTHBOUND
781	SY	BRIDGE 77 SOUTHBOUND
3,806	SY	SUBTOTAL
44	SY	ROUNDING
3,850	SY	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: COLCHESTER
PROJECT NUMBER: IM SURF(12)

FILE NAME: /pave/08al54/p08al54.dgn
PROJECT LEADER: WOOLAVER
DESIGNED BY: JLR
p08al54qs.1

PLOT DATE: 01-JUN-2009
DRAWN BY: JLR
CHECKED BY:
SHEET 5 OF 11