QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

		BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			10,000		10,000	LF	SHOULDER BERM REMOVAL	203.40	EST
			1		1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-
			250		250	CWT	EMULSIFIED ASPHALT	404.65	EST
			1		1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
			20,000		20,000	LB	BITUMINOUS CRACK SEALING, '' BLOW AND GO'' METHOD	417.20	EST
		280			280	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	EST
		100			100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST
			465		465	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
			1,000		1,000	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
			500		500	HR	FLAGGERS	630.15	EST
				1	1	LS	FIELD OFFICE, ENGINEERS	631.10	-
				1	1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
				1	1	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-
			1		1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
			1		1	LS	TRAFFIC CONTROL	641.10	-
			5 ~~11~~		5 ~~11~~	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
			257,000		257,000	LF	6 INCH WHITE LINE	646.214	-
			203,000		203,000	LF	6 INCH YELLOW LINE	646.215	-
			16,300		16,300	LF	12 INCH WHITE LINE	646.24	-
			257,000		257,000	LF	TEMPORARY 6 INCH WHITE LINE, PAINT	646.622	-
			203,000		203,000	LF	TEMPORARY 6 INCH YELLOW LINE, PAINT	646.632	-
			16,300		16,300	LF	TEMPORARY 12 INCH WHITE LINE, PAINT	646.662	-
			5,000		5,000	EA	LINE STRIPING TARGETS	646.76	EST
			66,500		66,500	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	EST
			1		1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
			1		1	LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.)	900.650	-
			1,000		1,000	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680	EST
			30		30	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE SURFACE PREPARATION, TYPE I)	900.680	EST
			6,750		6,750	TON	SPECIAL PROVISION (MICROSURFACE TREATMENT , TYPE II)	900.680	57
			5,450		5,450	CWT	SPECIAL PROVISION (FOG SEAL SURFACE TREATMENT)	900.683	28

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		MICRO – SURFACE, TYPE II
5,948	TON	MAINLINE
78	TON	EXIT 19
179	TON	EXIT 20
270	TON	EXIT 21
106	TON	EXIT 22
113	TON	EXIT 23
57	TON	ROUNDING
6,750	TON	TOTAL
		FOG SEAL SURFACE TREATMENT
5,000	CWT	MAINLINE
51	CWT	EXIT 19
118	CWT	EXIT 20
107	CWT	EXIT 21
70	CWT	EXIT 22
75	CWT	EXIT 23
28	CWT	ROUNDING
5,450	CWT	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME:	WATERFORD - LYNDON
PROJECT NUMBER:	IM SURF (14)
FILE NAME: 08a172\p08a172.dgn	PLOT DATE: 18-MAR-2010 15:55
PROJECT LEADER: DOMEY	DRAWN BY: WILDER
DESIGNED BY: WILDER	CHECKED BY: PAVT MGMT
IPARM FILE NAME: p08a172#5.i	SHEET 5 OF 17