

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
	ROADWAY	I-89 - BRIDGE NO. 58N	I-89 - BRIDGE NO. 86N	I-89 - BRIDGE NO. 94S	I-89 - BRIDGE NO. 98S	I-89 - BRIDGE NO. 100N	I-89 - BRIDGE NO. 100S	FULL C E ITEMS		GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
	1									1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
		145	406	259	175	87	87			1159		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
		3	5	2	2	2	2			16		CWT	EMULSIFIED ASPHALT	404.65				
		296	423	126	118	168	168			1299		TON	MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT	406.27				
		1	1	1	1	1	1			6		LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	406.29				
	1									1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
		53	55	20	16	26	26			196		GAL	WATER REPELLENT, SILANE	514.10				
			270	38	120	90	90			608		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
		1860	2507	490	540	990	990			7377		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
		60	60	76	60	60	60			376		LF	JOINT SEALER, HOT Poured	524.11				
		1924	2571	566	604	1054	1054			7773		SY	REMOVAL OF BRIDGE PAVEMENT	529.10				
					27					27		SY	REMOVAL OF CONCRETE OR MASONRY	529.26				
		10	10	2	2	2	2			28		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS I	580.10				
		10	10	2	2	2	2			28		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS II	580.11				
		1	2					1		4		CY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS III	580.12				
		16740	22560	4408	4860	8910	8910			66388		SF	SURFACE PREPARATION FOR MEMBRANE	580.16				
		10	10	10	10	10	10			60		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20				
		120	180	60	60	60	60			540		HR	TRUCK-MOUNTED ATTENUATOR	608.45				
		150	150	150	150	150	150			900		LF	TEMPORARY TRAFFIC BARRIER	621.90				
		150	150	150	150	150	150			900		LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95				
		120	180	60	60	60	60			540		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
								1		1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
	1									1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
						1				1		LS	TRAFFIC CONTROL (I-89 - BRIDGE NO. 100N)	641.10				
							1			1		LS	TRAFFIC CONTROL (I-89 - BRIDGE NO. 100S)	641.10				
		1								1		LS	TRAFFIC CONTROL (I-89 - BRIDGE NO. 58N)	641.10				
			1							1		LS	TRAFFIC CONTROL (I-89 - BRIDGE NO. 86N)	641.10				
				1						1		LS	TRAFFIC CONTROL (I-89 - BRIDGE NO. 94S)	641.10				
					1					1		LS	TRAFFIC CONTROL (I-89 - BRIDGE NO. 98S)	641.10				
		1	1	1	1	1	1			6		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
		1	1	1	1	1	1			6		EACH	PORTABLE ARROW BOARD	641.16				
		785	1165	295	328	434	434			3441		LF	6 INCH WHITE LINE	646.214				
		628	932	241	262	347	347			2757		LF	6 INCH YELLOW LINE	646.215				
		785	1165	295	328	434	434			3441		LF	TEMPORARY 6 INCH WHITE LINE	646.620				
		1175	1175	1175	1175	1175	1175			7050		LF	TEMPORARY 6 INCH WHITE LINE, TYPE II TAPE	646.621				
		628	932	241	262	347	347			2757		LF	TEMPORARY 6 INCH YELLOW LINE	646.630				
		1175	1175	1175	1175	1175	1175			7050		LF	TEMPORARY 6 INCH YELLOW LINE, TYPE II TAPE	646.631				
		59	88	23	25	33	33			261		EACH	LINE STRIPING TARGETS	646.76				
		75	75	75	75	75	75			450		SF	PAVEMENT MARKING MASK	646.86				
	1									1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				

