

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								1			1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I)	204.22				
									4748		4748		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
									80		80		CWT	EMULSIFIED ASPHALT	404.65				
									2756		2756		TON	MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT	406.27				
									10		10		LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I)	406.29				
								1			1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I)	406.50				
									420		420		GAL	WATER REPELLENT, SILANE	514.10				
									724		724		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
									14921		14921		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
									722		722		LF	JOINT SEALER, HOT POURED	524.11				
									17250		17250		SY	REMOVAL OF BRIDGE PAVEMENT	529.10				
									548		548		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS I	580.10				
									168		168		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS II	580.11				
									215		215		CY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS III	580.12				
									134292		134292		SF	SURFACE PREPARATION FOR MEMBRANE	580.16				
									200		200		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20				
									50		50		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25				
									50		50		HR	TRUCK RENTAL	608.37				
									1080		1080		HR	TRUCK-MOUNTED ATTENUATOR	608.45				
									20		20		EACH	ENERGY ABSORPTION ATTENUATOR	621.56				
									6250		6250		LF	TEMPORARY TRAFFIC BARRIER	621.90				
									6250		6250		LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95				
									7200		7200		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
								1			1		LS	MOBILIZATION/DEMobilIZATION	635.11				
									1		1		LS	TRAFFIC CONTROL (I-89 - BRIDGE NO. 15N)	641.10				
									1		1		LS	TRAFFIC CONTROL (I-89 - BRIDGE NO. 15S)	641.10				
									1		1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 41C)	641.10				
									1		1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 41N)	641.10				
									1		1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 41S)	641.10				
									1		1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 42N)	641.10				
									1		1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 42S)	641.10				
									1		1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 43S)	641.10				
									1		1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 44N)	641.10				
									1		1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 44S)	641.10				
									10		10		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
									10		10		EACH	PORTABLE ARROW BOARD	641.16				
									7294		7294		LF	6 INCH WHITE LINE	646.214				
									5833		5833		LF	6 INCH YELLOW LINE	646.215				
									75		75		LF	12 INCH WHITE LINE	646.24				

PROJECT NAME: HARTFORD - SHARON
PROJECT NUMBER: IM MEMB (15)

FILE NAME: ...03-05 quantity sheets.dgn PLOT DATE: 8/13/2009
PROJECT LEADER: G. BOGUE DRAWN BY: E. ALLING
DESIGNED BY: M. CHENETTE CHECKED BY: G. BOGUE
QUANTITY SHEET 1 SHEET 3 OF 47

