

BRIDGE QUANTITY SHEET 1

SUMMARY OF BRIDGE QUANTITIES										TOTALS	DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
I91 - BRIDGE NO. 41N	I91 - BRIDGE NO. 41S	I91 - BRIDGE NO. 41C	I91 BRIDGE NO. 42N	I91 - BRIDGE NO. 42S	I91 - BRIDGE NO. 43S	I91 - BRIDGE NO. 44N	I91 - BRIDGE NO. 44S	I91 - BRIDGE NO. 15N	I91 - BRIDGE NO. 15S	BRIDGE TOTAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
286	287	195	409	595	639	650	657	496	534	4748	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10			
3	3	3	8	9	6	19	19	5	5	80	CWT	EMULSIFIED ASPHALT	404.65			
115	107	118	310	304	213	621	612	178	178	2756	TON	MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT	406.27			
1	1	1	1	1	1	1	1	1	1	10	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	406.29			
31	35	28	33	36	22	97	96	21	21	420	GAL	WATER REPELLENT, SILANE	514.10			
40	78	48	54	54	138	60	60	96	96	724	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10			
473	418	608	1615	1521	943	3993	3927	695	728	14921	SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20			
76	76	48	84	84	84	60	60	75	75	722	LF	JOINT SEALER, HOT POURED	524.11			
672	615	733	1948	1855	1206	4143	4070	1007	1001	17250	SY	REMOVAL OF BRIDGE PAVEMENT	529.10			
5	5	5	9	9	5	250	250	5	5	548	SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS I	580.10			
5	5	5	9	9	5	60	60	5	5	168	SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS II	580.11			
10	10	10	18	17	10	60	60	10	10	215	CY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS III	580.12			
4256	3762	5472	14532	13692	8484	35940	35340	6258	6556	134292	SF	SURFACE PREPARATION FOR MEMBRANE	580.16			
10	10	10	10	10	10	60	60	10	10	200	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20			
5	5	5	5	5	5	5	5	5	5	50	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25			
5	5	5	5	5	5	5	5	5	5	50	HR	TRUCK RENTAL	608.37			
60	60	60	120	120	100	180	180	100	100	1080	HR	TRUCK-MOUNTED ATTENUATOR	608.45			
2	2	2	2	2	2	2	2	2	2	20	EACH	ENERGY ABSORPTION ATTENUATOR	621.56			
325	320	450	570	550	425	1420	1400	390	400	6250	LF	TEMPORARY TRAFFIC BARRIER	621.90			
325	320	450	570	550	425	1420	1400	390	400	6250	LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95			
230	200	300	780	730	450	1920	1900	330	360	7200	HR	UNIFORMED TRAFFIC OFFICERS	630.10			
								1		1	LS	TRAFFIC CONTROL (I-89 - BRIDGE NO. 15N)	641.10			
									1	1	LS	TRAFFIC CONTROL (I-89 - BRIDGE NO. 15S)	641.10			
		1								1	LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 41C)	641.10			
1										1	LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 41N)	641.10			
	1									1	LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 41S)	641.10			
			1							1	LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 42N)	641.10			
				1						1	LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 42S)	641.10			
					1					1	LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 43S)	641.10			
						1				1	LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 44N)	641.10			
							1			1	LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 44S)	641.10			
1	1	1	1	1	1	1	1	1	1	10	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15			
1	1	1	1	1	1	1	1	1	1	10	EACH	PORTABLE ARROW BOARD	641.16			
290	274	435	633	658	503	1798	1773	460	470	7294	LF	6 INCH WHITE LINE	646.214			
232	219	348	506	526	402	1438	1418	368	376	5833	LF	6 INCH YELLOW LINE	646.215			
			75							75	LF	12 INCH WHITE LINE	646.24			
290	274	435	633	658	503	1798	1773	460	470	7294	LF	TEMPORARY 6 INCH WHITE LINE	646.620			
1240	2240	1360	1800	2060	1930	2330	2310	1300	3180	19750	LF	TEMPORARY 6 INCH WHITE LINE, TYPE II TAPE	646.621			
232	219	348	506	526	402	1438	1418	368	376	5833	LF	TEMPORARY 6 INCH YELLOW LINE	646.630			
1240	1230	1360	1480	1460	1330	2330	2310	1300	1310	15350	LF	TEMPORARY 6 INCH YELLOW LINE, TYPE II TAPE	646.631			

PROJECT NAME: HARTFORD - SHARON
PROJECT NUMBER: IM MEMB (15)

FILE NAME: ...03-05 quantity sheets.dgn PLOT DATE: 8/13/2009
PROJECT LEADER: G. BOGUE DRAWN BY: E. ALLING
DESIGNED BY: M. CHENETTE CHECKED BY: G. BOGUE
BRIDGE QUANTITY SHEET 1 SHEET 5 OF 47

