

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY	BRIDGE NO. 59S	BRIDGE NO. 60S	BRIDGE NO. 64S	FULL C.E. ITEMS	BRIDGE NO. 64N	BRIDGE NO. 67N	BRIDGE NO. 69N	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS		
1								1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22						
	438	438	326		245	437	592	2476	NO	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10						
	4	3	2.3		1.9	4.5	2.1	17.8		CWT	EMULSIFIED ASPHALT	404.65						
	259	191	148		120	298	132	1148	YES	TON	MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT	406.27						
	1	1	1		1	1	1	6		LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	406.29						
1								1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50						
	23	44	21		25	26	21	160		GAL	WATER REPELLENT, SILANE	514.10						
	80	43	52		52	40	76	343		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10						
	1185	700	522		400	1460	389	4656		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20						
	1447	962	766		644	1722	389	5930		SY	REMOVAL OF BRIDGE PAVEMENT	529.10						
			10			10		20		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS II	580.11						
			4		4	4		12		CY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS III	580.12						
	10657	6294	4694		3594	13134	3497	41870		SF	SURFACE PREPARATION FOR MEMBRANE	580.16						
	10	10	10		10	10	10	60		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20						
	240	120	180		180	300	120	1140		HR	TRUCK-MOUNTED ATTENUATOR	608.45						
	2		2			2		6		EACH	ENERGY ABSORPTION ATTENUATOR	621.56						
	360	360	360		360	360	360	2160		LF	TEMPORARY TRAFFIC BARRIER	621.90						
	360	360	360		360	360	360	2160		LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95						
	240	120	180		180	300	120	1140		HR	UNIFORMED TRAFFIC OFFICERS	630.10						
		150	150		150		150	600		HR	FLAGGERS	630.15						
				1				1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17						
1								1		LS	MOBILIZATION/DEMobilIZATION	635.11						
	0.5	0.5						1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 59S AND 60S)	641.10						
					1			1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 64N)	641.10						
			1					1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 64S)	641.10						
						1		1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 67N)	641.10						
							1	1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 69N)	641.10						
	0.5	0.5	1		1	1	1	5		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15						
	0.5	0.5	1		1	1	1	5		EACH	PORTABLE ARROW BOARD	641.16						
	539	400	335		273	618	291	2456		LF	6 INCH WHITE LINE	646.214						
	431	320	268		218	494	233	1964		LF	6 INCH YELLOW LINE	646.215						
	2485	1385	1385		1385	3085	1385	11110		LF	TEMPORARY 6 INCH WHITE LINE, TYPE II TAPE	646.621						
	1385	1385	1385		1385	1385	1385	8310		LF	TEMPORARY 6 INCH YELLOW LINE, TYPE II TAPE	646.631						
						290		290		LF	TEMPORARY 12 INCH WHITE LINE, TYPE II TAPE	646.661						
	11	8	7		6	13	6	51		EACH	LINE STRIPING TARGETS	646.76						
	75	75	75		75	75	75	450		SF	PAVEMENT MARKING MASK	646.86						
1								1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50						