

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
		ROADWAY	BRIDGE NO. 70N	BRIDGE NO. 71N	BRIDGE NO. 74N	BRIDGE NO. 76N	BRIDGE NO. 77N	BRIDGE NO. 78N	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
		1								1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
			254	549	845	652	204	326		2830	NO	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
			1.8	2.2	2.9	3.8	4.6	3.5		18.8		CWT	EMULSIFIED ASPHALT	404.65				
			115	141	185	251	303	230		1225	YES	TON	MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT	406.27				
			1	1	1	1	1	1		6		LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	406.29				
		1								1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
			23	20	49	26	35	22		175		GAL	WATER REPELLENT, SILANE	514.10				
			86	38	53	65		47		289		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
			348	494	511	1168	1746	1103		5370		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
			601	494	511	1168	1991	1347		6112		SY	REMOVAL OF BRIDGE PAVEMENT	529.10				
				10		10				20		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS II	580.11				
					4	4	4			12		CY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS III	580.12				
			3127	4446	4597	10512	15712	9919		48313		SF	SURFACE PREPARATION FOR MEMBRANE	580.16				
			10	10	10	10	10	10		60		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20				
			120	120	180	300	300	240		1260		HR	TRUCK-MOUNTED ATTENUATOR	608.45				
				2		2		2		6		EACH	ENERGY ABSORPTION ATTENUATOR	621.56				
			360	360	360	360	360	360		2160		LF	TEMPORARY TRAFFIC BARRIER	621.90				
			360	360	360	360	360	360		2160		LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95				
			120	120	180	300	300	240		1260		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
			150	150	150	150	150	150		900		HR	FLAGGERS	630.15				
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
									1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
									1	1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25				
		1								1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
			1							1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 70N)	641.10				
				1						1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 71N)	641.10				
					1					1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 74N)	641.10				
						1				1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 76N)	641.10				
							0.5	0.5		1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 77N AND 78N)	641.10				
			1	1	1	1	0.5	0.5		5		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
			1	1	1	1	0.5	0.5		5		EACH	PORTABLE ARROW BOARD	641.16				
			253	309	402	559	674	514		2711		LF	6 INCH WHITE LINE	646.214				
			203	247	321	447	539	411		2168		LF	6 INCH YELLOW LINE	646.215				
			1385	1385	1385	1385	1385	1385		8310		LF	TEMPORARY 6 INCH WHITE LINE, TYPE II TAPE	646.621				
			1385	1385	1385	1385	1385	1385		8310		LF	TEMPORARY 6 INCH YELLOW LINE, TYPE II TAPE	646.631				
			6	7	9	12	14	11		59		EACH	LINE STRIPING TARGETS	646.76				
			75	75	75	75	75	75		450		SF	PAVEMENT MARKING MASK	646.86				
		1								1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				