



# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
					ROADWAY	EROSION CONTROL	I91 - BR. NO. 96-2N	I91 - BR. NO. 96-2S	I91 - BR. NO. 111-1	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					1						1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
							15	15	20		50		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
					1						1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
							84	79	83		246		CY	STRUCTURE EXCAVATION	204.25				
							72	81	89		242		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
							3985	4764	2551		11300		LB	REINFORCING STEEL	507.15				
								42	49		91		LF	DRILLING AND GROUTING DOWELS	507.16				
							1.8	1.8	2.2		5.8		GAL	WATER REPELLENT, SILANE	514.10				
							5	9	13		27		CY	REMOVAL OF CONCRETE OR MASONRY	529.25				
							26	30	36		92		CY	CONCRETE, CLASS B	541.25				
							9	9	13		31		CY	CONCRETE, CLASS C	541.30				
							5	5	10		20		CY	CONCRETE, CLASS D	541.31				
							20	20	20		60		CY	STONE FILL, TYPE II	613.11				
							7	8	8		23		CY	STONE FILL, TYPE IV	613.13				
					80						80		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
					1						1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
							1				1		LS	TRAFFIC CONTROL (I91 - BR. NO. 96-2N)	641.10				
								1			1		LS	TRAFFIC CONTROL (I91 - BR. NO. 96-2S)	641.10				
									1		1		LS	TRAFFIC CONTROL (I91 - BR. NO. 111-1)	641.10				
					4						4		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
					4						4		EACH	PORTABLE ARROW BOARD	641.16				
							30	32	35		97		SY	GEOTEXTILE UNDER STONE FILL	649.31				
						125					125		SY	GEOTEXTILE FOR SILT FENCE	649.51				
						1					1		LB	SEED	651.15				
						11					11		LB	FERTILIZER	651.18				
						0.05					0.05		TON	AGRICULTURAL LIMESTONE	651.20				
						0.05					0.05		TON	HAY MULCH	651.25				
						6.2					6.2		CY	TOPSOIL	651.35				
						1					1		LS	EPSC PLAN	652.10				
						32					32		HR	MONITORING EPSC PLAN	652.20				
						1					1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
						110					110		SY	PERMANENT EROSION MATTING	653.21				
						1685					1685		LF	PROJECT DEMARCATION FENCE	653.55				
							5	5	10		20		CY	SPECIAL PROVISION (CONTROLLED DENSITY (FLOWABLE) FILL)	900.608				
							187	201			388		LF	SPECIAL PROVISION (ALUMINUM PIPE LINER) (60") (72" EXISTING PIPE)	900.640				
									783		783		LF	SPECIAL PROVISION (ALUMINUM PIPE LINER) (72") (84" EXISTING PIPE)	900.640				
							100	100	200		400		LF	SPECIAL PROVISION (TEST BORINGS)	900.640				

PROJECT NAME: **LYNDON - DERBY**  
PROJECT NUMBER: **IM CULV (19)**  
FILE NAME: **Quantity Sheet**      PLOT DATE: **08/24/2009**  
PROJECT MANAGER: **DMB**      DRAWN BY: **RPH**  
DESIGNED BY: **RPH**      CHECKED: **BRC**  
**QUANTITY SHEET #1**      SHEET **4** OF **28**