

LOCATION	676.10				676.12		676.20		REMARKS
	TYPE I GUARD RAIL ENDS	TYPE I RAMPS	TYPE II	TYPE III	TYPE I WITH PLAQUE	TYPE I WITHOUT PLAQUE	REMOVAL OF EXISTING DELINEATOR	DELINEATOR WITH FLEXIBLE POST	
	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	
NORTHBOUND	152		780		780		1712		BEGIN AT MM 90.90 END AT MM 129.95
SOUTHBOUND	216		780		780		1776		BEGIN AT MM 129.95 END AT MM 90.90
INTERCHANGE 17		24	6	18			48		
INTERCHANGE 19		62	20	16			110	12	
INTERCHANGE 20		22	28	16			66		
INTERCHANGE 21		20	35	8			63		
INTERCHANGE 22		27	26	10			63		
NB REST AREA			16				16		
SB REST AREA			16				16		
TOTAL	368	155	1707	68	1560		3870	12	

TABLE OF DELINEATOR QUANTITIES

SEEDING FORMULA

% BY WEIGHT	LBS/ACRE	NAME	PURITY (%)	GERMINATION (%)
37.5	22.5	CREeping RED FESCUE	98	85
37.5	22.5	TALL FESCUE	95	90
5.0	3.0	RED TOP	95	90
15.0	9.0	BIRDSFOOT TREFOIL	98	85
5.0	3.0	ANNUAL RYEGRASS	95	85
100.0	60.0			

SEEDING NOTES:

- 1) SEED MIXTURE SHALL NOT HAVE A WEED CONTENT EXCEEDING 0.40% BY WEIGHT AND SHALL BE FREE OF ALL NOXIOUS SEED.
- 2) SEED IS TO BE APPLIED PER SEEDING FORMULA OR AS DIRECTED BY THE ENGINEER.
- 3) HAY MULCH IS TO BE PLACED ON SEEDED AREAS AT THE RATE OF 2 TONS/ACRE, OR AS DIRECTED BY THE ENGINEER.

**MISCELLANEOUS
DETAILS**

PROJECT NAME: COLCHESTER-HIGHGATE	PLOT DATE: 8/21/2009
PROJECT NUMBER: IMG SIGN (17)	DRAWN BY: BMB
FILE NAME: 09A016.DGN	CHECKED BY: EPD
PROJECT LEADER: EPD	SHEET 4 OF 221
DESIGNED BY: BMB	
PLOT FILE: 09A016MISCDET.L	