STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
NORTHBOUND MM 92.000 RT	MILE 92	1	12	36	3.00						1					X		X																DIO-2		SHS
NORTHBOUND MM 92.060 RT	GROOVED SHOULDER	1 1	48 24	48 18	16.00 3.00						2						X	X															VW-397 VP-396 MOUNT VW-397 ABOVE VP-396	46	E-153B
NORTHBOUND MM 92.155 RT	SPEED LIMIT 65 MINIMUM 40	1 1	48 48	60 48	20.00 16.00						2												2		X								R2-1 VR-141 MOUNT R2-1 ABOVE VR-141		SHS E-142
NORTHBOUND MM 92.470 RT	Lake Champlain Islands 12 St. Albans 24	1	204	42		59.50	R				2																	2		210	W6X9		D2-2 FUSE PLATE BOLT TENSION = 12.0 KIPS	27	
NORTHBOUND MM 92.720 LT & RT	KEEP RIGHT EXCEPT TO PASS	2	48	60	40.00						4												4	X									VR-132	47	
NORTHBOUND MM 92.950 RT	BRIDGE 74-1 I-89	1	6	10	0.42						1				X			X															VD-701		E-134
NORTHBOUND MM 93.000 RT	MILE 93	1	12	36	3.00						1					X		X															DIO-2		SHS
NORTHBOUND MM 93.422 RT	BRIDGE 74-2 I-89	1	6	10	0.42						1				X			X															VD-701		E-134
NORTHBOUND MM 93.447 RT	BRIDGE 75 I-89	1	6	10	0.42						1				X			X															VD-701		E-134
NORTHBOUND MM 93.623 RT	BRIDGE 75-1N I-89	1	6	10	0.42						1				X			X															VD-701		E-134
												FT	FT	FT	FT 32	FT 19.5	FT 30		EA	LB	LB	LB		LB 456	LB 270	LB	LB								
					SF 102.68	SF 59.50	EA. 1	SF				FT			FT 81.50					LB			EA. 6		LB 726			EA. 2	EA.	LB. 210					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

NORTHBOUND TRAFFIC SIGN SUMMARY SHEET 2

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSSNB2.I

PLOT DATE: 8/21/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 63 OF 221