STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REMOVED & RECOVERED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
NORTHBOUND MM 101.601 LT & RT		1 1	12 12	36 36	3.00 3.00						1 1					X X		X X																	OM-3L OM-3R		SHS SHS
NORTHBOUND MM 102.250 RT		1	48	48	16.00						2						X	X																VW-285	46	
NORTHBOUND MM 103.536 RT		1	6	10	0.42						1				X			X																VD-701		E-134
NORTHBOUND MM 104.695 RT		1	6	10	0.42						1				X			X																VD-701		E-134
NORTHBOUND MM 105.230 RT		1	96	30	20.00						2																		2		1290	W10x26		EI-5 FUSE PLATE BOLT TENSION = 28.4 KIPS	29	
		1	204	156		221.00	R R																											EI-2	29	
NORTHBOUND MM 105.369 RT		1	6	10	0.42						1				X			X																VD-701		E-134
NORTHBOUND MM 105.620 RT		1	6	10	0.42						1				X			X																VD-701		E-134
NORTHBOUND MM 105.625 LT & RT		1 1	12 12	36 36	3.00 3.00						1 1					X X		X X																OM-3L OM-3R		SHS SHS
					SF 49.68	SF 221.00	EA. 2	SF				FT	FT	FT	FT 32	FT 60	FT 30		EA	LB	LB	LB		LB	LB	LB	LB	EA. 2	EA.	LB. 1290					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND *SIGN POST DESIGN GUIDELINE*.

FT 122 | LB | LB

NORTHBOUND TRAFFIC SIGN SUMMARY SHEET 7

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSSNB7.i

PLOT DATE: 8/21/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 68 OF 221