STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																					REMARKS	SIGN DETAIL	
		EA	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft			SQUARE STEEL (in) lb/ft			ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft			FOUNDATION	TUBULAR STEEL Ø (in) lb/ft				W-SHAPE STEEL FTG. SIZE		WEIGHT	POST SIZE	SIGN FRAME REQUIRED		DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												1.12	2.0	3.0	1.75	2.0	2.5			3.0	4.0	4.0 MOD		3.0	3.5	4.0	5.0	24"	30"						
															1.88	2.42	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6								
											OPTION ITEMS																								
NORTHBOUND MM 110.240 RT	REST AREA	1	78	78		42.25	R				2												2		X							D5-2B		SHS
NORTHBOUND MM 110.370 RT		1	48	48	16.00						2						X	X														W4-1R		SHS
NORTHBOUND MM 110.371 RT	BRIDGE 86-4N I-89	1	6	10	0.42						1				X			X														VD-701		E-134
NORTHBOUND MM 110.435 LT	ONE WAY	1	36	12	3.00						2					X		X														R6-1R		SHS
NORTHBOUND MM 110.830 RT	ENTERING TOWN OF FAIRFAX	1	42	30	8.75						2					X		X														I-2		E-131
NORTHBOUND MM 111.000 RT	MILE 111	1	12	48	4.00						1					X		X														D10-3		SHS
NORTHBOUND MM 111.140 LT		1	36	36	9.00						2					X		X														R3-4		SHS
NORTHBOUND MM 111.299 RT	BRIDGE 86-5 I-89	1	6	10	0.42						1				X			X														VD-701		E-134
NORTHBOUND MM 111.300 LT & RT		1	12	36	3.00						1					X		X														OM-3L		SHS
		1	12	36	3.00						1					X		X														OM-3R		SHS
NORTHBOUND MM 111.351 RT	BRIDGE 87N I-89	1	6	10	0.42						1				X			X														VD-701		E-134
							1					FT	FT	FT	FT 24	FT 129.75	FT 30		EA	LB	LB	LB		LB	LB 270	LB	LB							
			SF 48.01	SF 42.25	EA.	SF						FT			FT 183.75					LB			EA. 2	LB 270				EA.	EA.	LB.				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

NORTHBOUND TRAFFIC SIGN SUMMARY SHEET 12

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSSNB12.I
PLOT DATE: 8/21/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 73 OF 221