STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	SQUARE STEEL (in) lb/ft 2.0 2.42	SQUARE STEEL (in) lb/ft 2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 1.7	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
OPTION ITEMS																																			
NORTHBOUND MM 116.000 RT	MILE 116	1	12	48	4.00						1					X		X																DI0-3		SHS
NORTHBOUND MM 116.510 RT	EXIT 20	1	96	30	20.00						2																	2		700	W8X18		EI-5 FUSE PLATE BOLT TENSION = 20.5 KIPS	33	
	7 VERMONT 207 St. Albans 1 MILE	1	174	126		152.25	R R																										EI-2	33	
NORTHBOUND MM 116.760 RT	BRIDGE 92N I-89	1	6	10	0.42						1				X			X															VD-70I		E-134
NORTHBOUND MM 116.760 LT & RT		1 1	12 12	36 36	3.00 3.00						1 1					X X		X X															OM-3L OM-3R		SHS SHS
NORTHBOUND MM 116.950 RT	EXIT 20	1	96	30	20.00						2																	2		900	W8X21		EI-5 FUSE PLATE BOLT TENSION = 28.4 KIPS	34	
	7 VERMONT 207 St. Albans ½ MILE	1	174	126		152.25	0																										EI-2	34	
	NEXT EXIT 6 MILES	1	162	30		33.75	0																										E2-1	40	
NORTHBOUND MM 117.000 RT	MILE 117	1	12	48	4.00						1					X		X															DI0-3		SHS
							2					FT	FT	FT	FT 8	FT 49.5	FT		EA	LB	LB	LB		LB	LB	LB	LB								
					SF 54.42	SF 338.25	EA.	SF				FT			FT 57.5					LB			EA.	LB				EA. 4	EA.	LB. 1600					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

NORTHBOUND TRAFFIC SIGN SUMMARY SHEET 17

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSSNBI7.I

PLOT DATE: 8/21/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 78 OF 221