STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.42	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	REFRAME SIGN REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
NORTHBOUND MM 118.630 LT & RT	KEEP RIGHT EXCEPT TO PASS	2	48	60	40.00						4												4	X										VR-132	47	
NORTHBOUND MM 119.000 RT	MILE 119	1	12	48	4.00						1					X		X																DIO-3		SHS
NORTHBOUND MM 120.000 RT	MILE 120	1	12	48	4.00						1					X		X																DIO-3		SHS
NORTHBOUND MM 120.270 RT		1	36	36	9.00						2					X		X																R3-4		SHS
NORTHBOUND MM 121.000 RT	MILE 121	1	12	48	4.00						1					X		X																DIO-3		SHS
NORTHBOUND MM 121.330 RT	BRIDGE 94N I-89	1	6	10	0.42						1				X			X																VD-701		E-134
NORTHBOUND MM 121.330 LT & RT		1 1	12 12	36 36	3.00 3.00						1 1					X X		X X																OM-3L OM-3R		SHS SHS
NORTHBOUND MM 122.000 RT	MILE 122	1	12	48	4.00						1					X		X																DIO-3		SHS
NORTHBOUND MM 122.280 RT	EXIT 21	1	96	30	20.00						2																	2		740	W8X18		EI-5 FUSE PLATE BOLT TENSION = 19.2 KIPS	35	
	VERMONT 78 / 7 Swanton 1 MILE	1	150	126		131.25	R R																											EI-2	35	
							2					FT	FT	FT	FT 8	FT 99.00	FT		EA	LB	LB	LB		LB 456	LB	LB	LB								
					SF 91.42	SF 131.25	EA.	SF				FT			FT 107.00					LB			EA. 4	LB 456				EA. 2	EA.	LB. 740					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

NORTHBOUND TRAFFIC SIGN SUMMARY SHEET 20

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSSNB20.I

PLOT DATE: 8/21/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 81 OF 221