STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75 (1.88)	SQUARE STEEL (in) lb/ft 2.0 (2.42)	SQUARE STEEL (in) lb/ft 2.5 (3.35)	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 (1.3)	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 (1.7)	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD (1.7)	FOUNDATION	TUBULAR STEEL Ø (in) lb/ft 3.0 (7.6)	TUBULAR STEEL Ø (in) lb/ft 3.5 (9.0)	TUBULAR STEEL Ø (in) lb/ft 4.0 (10.8)	TUBULAR STEEL Ø (in) lb/ft 5.0 (14.6)	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STD. SHEET NUMBER
												OPTION ITEMS																							
NORTHBOUND MM 128.000 RT	MILE 128	1	12	48	4.00						1					X		X																D10-3		SHS
NORTHBOUND MM 128.230 RT	Canada 2	1	84	24	14.00						2						X	X																D2-1	37	
NORTHBOUND MM 128.260 LT		1	36	36	9.00						2					X		X																R3-4		SHS
NORTHBOUND MM 128.320 RT	ROCK RIVER	1	36	24	6.00						2					X		X																I-3		E-131
NORTHBOUND MM 128.335	BRIDGE 100N I-89	1	6	10	0.42						1				X			X																VD-701		E-134
NORTHBOUND MM 128.340 LT & RT		1 1	12 12	36 36	3.00 3.00						1 1					X X		X X																OM-3L OM-3R		SHS SHS
NORTHBOUND MM 128.450 LT		1	36	36	9.00						2					X		X																R3-4		SHS
NORTHBOUND MM 128.970 LT		1	36	36	9.00						2					X		X																R3-4		SHS
NORTHBOUND MM 128.980 RT	EXIT 22	1	96	30	20.00						3																	3		1785	W10x26		E1-5 FUSE PLATE BOLT TENSION = 28.4 KIPS	38	
	7 SOUTH Highgate Springs ¾ MILE	1	270	120		225.00	R																											E1-2	38	
							1					FT	FT	FT	FT 8	FT 159.75	FT 30		EA	LB	LB	LB		LB	LB	LB	LB								
					SF 77.42	SF 225.00	EA.	SF				FT			FT 197.75					LB			EA.	LB				EA. 3	EA.	LB. 1785					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

NORTHBOUND TRAFFIC SIGN SUMMARY SHEET 25

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSSNB25.1

PLOT DATE: 8/21/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 86 OF 221