STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.42	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
SOUTHBOUND MM 128.960 RT	STATE LAW STOP FOR SCHOOL BUS FLASHING RED LIGHTS / ARRETT OBLIGATIORE SURFEU ROUGE D'AUTOBUS D'ECOLIERS	1 1	48 48	60 60	20.00 20.00						2												2		X								VR-048 MOUNT VR-048 ABOVE VR-048 (FRENCH) VR-048 (FRENCH)		E-144 E-144
SOUTHBOUND MM 128.746 RT	BRIDGE 101 I-89	1	6	10	0.42						1				X			X																VD-701		E-134
SOUTHBOUND MM 128.650 RT 128.49	Swanton 6 St. Albans 12 STATE LAW	1	114 132	42 66		33.25 60.5					2																	2		290	W6X9		D2-2 EXISTING SIGN AND HARDWARE TO BE REMOVED FROM BRIDGE FUSE PLATE BOLT TENSION = 12.0 KIPS MIN. 400, SOUTH OF 419	37	
SOUTHBOUND MM 128.480 LT		1	36	36	9.00						2					X		X																R3-4		SHS
SOUTHBOUND MM 128.430 RT	ROCK RIVER	1	36	24	6.00						2					X		X																I-3		E-131
SOUTHBOUND MM 128.412 RT	BRIDGE 100S I-89	1	6	10	0.42						1				X			X																VD-701		E-134
SOUTHBOUND MM 128.410 LT & RT		1 1	12 12	36 36	3.00 3.00						1 1					X X		X X																OM-3R OM-3L		SHS SHS
SOUTHBOUND MM 128.400 LT & RT	KEEP RIGHT EXCEPT TO PASS	2	48	60	40.00						4												4	X										VR-132	47	
SOUTHBOUND MM 128.285 LT		1	36	36	9.00						2					X		X																R3-4		SHS
SOUTHBOUND MM 128.000 RT	MILE 128	1	12	48	4.00						1					X		X																DI0-3		SHS
												FT	FT	FT	FT 16	FT 129.75	FT		EA	LB	LB	LB		LB 456	LB 270	LB	LB								
					SF 114.84	SF 33.25	EA.	SF				FT			FT 145.75					LB			EA. 6	LB 726				EA. 2	EA.	LB. 290					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

SOUTHBOUND TRAFFIC SIGN SUMMARY SHEET 3

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSSSB3.1
PLOT DATE: 8/20/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 96 OF 221