STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	REQUIRED SIGNS	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
SOUTHBOUND MM 127.700 RT	511 TRAVEL INFO	1	48	48	16.00						2						X	X															VD-123	41	
SOUTHBOUND MM 127.000 RT	MILE 127	1	12	48	4.00						1					X		X															DIO-3		SHS
SOUTHBOUND MM 126.000 RT	MILE 126	1	12	48	4.00						1					X		X															DIO-3		SHS
SOUTHBOUND MM 125.090 LT		1	36	36	9.00						2					X		X															R3-4		SHS
SOUTHBOUND MM 125.000 RT	MILE 125	1	12	48	4.00						1					X		X															DIO-3		SHS
SOUTHBOUND MM 124.560 RT	EXIT 21	1	96	30	20.00						2																	2		930	W8x21		E1-5 FUSE PLATE BOLT TENSION = 28.4 KIPS	35	
	VERMONT 78 7 Swanton 1 MILE	1	150	126		131.25																											E1-2	35	
SOUTHBOUND MM 124.250 RT	Highgate Center Lake Champlain Islands EXIT 21	1	288	84		168.00					3																	3		1020	W6x15		E3-1 FUSE PLATE BOLT TENSION = 19.2 KIPS	37	
		1	30	30	6.25																												I-5		SHS
					SF 63.25	SF 299.25	EA.	SF				FT	FT	FT	FT	FT 59.25	FT 30		EA	LB	LB	LB		LB	LB	LB	LB	EA. 5	EA.	LB. 1950					
												FT			FT 89.25					LB			EA.	LB											

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

SOUTHBOUND TRAFFIC SIGN SUMMARY SHEET 4

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSSS41.i

PLOT DATE: 8/20/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 97 OF 221