STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.88 (1.75)	2.42 (2.0)	3.35 (2.5)	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 1.3 (3.0)	1.7 (4.0)	1.7 (4.0 MOD)	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 7.6 (3.0)	9.0 (3.5)	10.8 (4.0)	14.6 (5.0)	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
SOUTHBOUND MM 123.470 RT	EXIT 21 ↗	1	72	60		30.00					2												2	X								E5-1A	40	
SOUTHBOUND MM 123.382 RT	BRIDGE 98S I-89	1	6	10	0.42						1				X			X														VD-701		E-134
SOUTHBOUND MM 123.380 LT & RT		1 1	12 12	36 36	3.00 3.00						1 1					X X		X X														OM-3R OM-3L		SHS SHS
SOUTHBOUND MM 123.275 RT		1	48	48	16.00						2						X	X														W4-1R		SHS
SOUTHBOUND MM 123.240 LT	ONE WAY	1	36	12	3.00						2					X		X														R6-1R		SHS
SOUTHBOUND MM 123.152 RT	BRIDGE 97S I-89	1	6	10	0.42						1				X			X														VD-701		E-134
SOUTHBOUND MM 123.150 LT & RT		1 1	12 12	36 36	3.00 3.00						1 1					X X		X X														OM-3R OM-3L		SHS SHS
SOUTHBOUND MM 123.05 RT	EMERGENCY STOPPING ONLY	1	48	36	12.00						2						X	X														R8-7		SHS
SOUTHBOUND MM 123.000 RT	MILE 123	1	12	48	4.00						1					X		X														D10-3		SHS
SOUTHBOUND MM 122.950 RT	SOUTH INTERSTATE 89	1 1	30 36	15 36	3.12 9.00						2						X	X														M3-3 WHITE ON BLUE MOUNT M3-3 ABOVE M1-1 M1-1		SHS SHS
					SF 59.96	SF 30.00	EA.	SF				FT	FT	FT	FT 16	FT 99.75	FT 90		EA	LB	LB	LB	EA. 2	LB 228	LB	LB	LB	EA.	EA.	LB.					
												FT			FT 205.75					LB															

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

SOUTHBOUND TRAFFIC SIGN SUMMARY SHEET 6

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSSSB6.i

PLOT DATE: 8/20/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 99 OF 221