STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
SOUTHBOUND MM 114.130 RT	EXIT 19	1	96	30	20.00						2																2		860	W8X21		EI-5 FUSE PLATE BOLT TENSION = 28.4 KIPS	33	
	7 VERMONT 36 VERMONT 104 St. Albans	1	234	102		165.75																										EI-1	33	
SOUTHBOUND MM 114.020 RT	EXIT 40 M.P.H.	1	36	48	12.00						2						X	X														WI3-2		SHS
SOUTHBOUND MM 114.000 RT	MILE 114	1	12	48	4.00						1					X		X														DI0-3		SHS
SOUTHBOUND MM 113.875 RT		1	18	18	2.25						1					X		X														OMI-1		SHS
SOUTHBOUND MM 113.870 RT	EXIT 19	1	72	60		30.00					2											2	X									E5-1A	40	
SOUTHBOUND MM 113.747 RT	BRIDGE 88S I-89	1	6	10	0.42						1				X			X														VD-701		E-134
SOUTHBOUND MM 113.740 LT & RT		1 1	12 12	36 36	3.00 3.00						1 1					X X		X X														OM-3L OM-3R REMOVE SIGN ON OPPOSITE SIDE OF BRIDGE		SHS SHS
					SF 44.67	SF 195.75	EA.	SF				FT	FT	FT	FT 8	FT 54.75	FT 30		EA	LB	LB	LB		LB 228	LB	LB	LB								
												FT			FT 92.75					LB			EA. 2	LB 228				EA. 2	EA.	LB. 860					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

SOUTHBOUND TRAFFIC SIGN SUMMARY SHEET 13

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSSSBI3.I

PLOT DATE: 8/20/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 106 OF 221