STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
SOUTHBOUND MM 100.000 RT	MILE 100	1	12	48	4.00						1					X		X															DI0-3		SHS
SOUTHBOUND MM 99.000 RT	MILE 99	1	12	36	3.00						1					X		X															DI0-2		SHS
SOUTHBOUND MM 98.940 RT	EXIT 17	1	96	30	20.00						3 ~~4~~																3		1530	W8X21		EI-5 FUSE PLATE BOLT TENSION = 34.5 KIPS	30	
	2 7 Lake Champlain Islands Colchester 1 MILE	1	360	156		390.00																											EI-2	30	
SOUTHBOUND MM 98.770 RT	New York State via Ferry or Bridge EXIT 17	1	240	84		140.00					2																2		570	W6x15		E3-1 FUSE PLATE BOLT TENSION = 19.2 KIPS	28	
SOUTHBOUND MM 98.630 RT	MOOSE NEXT 1 MILE	1 1	48 24	48 18	16.00 3.00						2						X	X															VW-001 MOUNT VW-001 ABOVE W7-3A W7-3A	46	SHS
SOUTHBOUND MM 98.470 RT	ENTERING TOWN OF COLCHESTER	1	42	30	8.75						2					X		X															I-2		E-131
SOUTHBOUND MM 98.440 RT	EXIT 17	1	96	30	20.00						4																4		2570	W10X26		EI-5 FUSE PLATE BOLT TENSION = 28.4 KIPS	29	
	2 7 Lake Champlain Islands Colchester ½ MILE	1	360	150		375.00																											EI-2	29	
	NEXT EXIT 6 MILES	1	162	30		33.75																											E2-1	40	
					SF 74.75	SF 938.75	EA.	SF				FT	FT	FT	FT	FT 49.5	FT 30		EA	LB	LB	LB		LB	LB	LB	LB								
												FT			FT 79.5					LB			EA.	LB				EA. 9	EA.	LB. 4670					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

SOUTHBOUND TRAFFIC SIGN SUMMARY SHEET 22

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSSSB22.1
PLOT DATE: 8/21/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 115 OF 221