STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.42	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	REFLECTIVE SIGNS REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
EXIT 16 ROOSEVELT HIGHWAY US ROUTE 2 / US ROUTE 7 MM. 0.205 RT (US ROUTE 7)	WEST 2 NORTH 7 Colchester	1	144	90		90.00																							225	6X15		MOUNT ON BRIDGE	42	
EXIT 16 ROOSEVELT HIGHWAY US ROUTE 2 / US ROUTE 7 MM. 0.205 RT (US ROUTE 7)	89 NORTH	1	102	72		51.00																										MOUNT ON BRIDGE	42	
EXIT 16 ROOSEVELT HIGHWAY US ROUTE 2 / US ROUTE 7 MM. 0.230 LT (US ROUTE 7)	EAST 2 SOUTH 7 Winooski	1	144	90		90.00																							225	6X15		MOUNT ON BRIDGE	42	
EXIT 16 ROOSEVELT HIGHWAY US ROUTE 2 / US ROUTE 7 MM. 0.230 LT (US ROUTE 7)	89 SOUTH	1	102	72		51.00																										MOUNT ON BRIDGE	42	
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".					SF	SF 282.00	EA.	SF				FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
												FT			FT					LB			EA.	LB				EA.	EA.	LB 450					

INTERCHANGE 16 TRAFFIC SIGN SUMMARY SHEET 1

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSS16-1.1

PLOT DATE: 8/21/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 126 OF 221