STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
	MILTON 5	1	72	12	6.00																													DI-1A		E-123
	CHAMPLAIN ISLANDS	1	72	12	6.00																													DI-1		E-123
	NY STATE VIA BRIDGE OR FERRY	1	72	12	6.00																													DI-1	45	
	SERVICES	1	72	10	5.00																													VD-502S	49	
	4 CAMPING 6	1	72	10	5.00																													VS-502C	49	
EXIT 17 RAMP D MM. 0.255 RT		1	36	36	9.00						2					X		X															W3-2		SHS
EXIT 17 RAMP D MM. 0.290 LT	MOUNTED BACK TO BACK	1 1	36 36	36 36	4.50 9.00						2					X		X															RI-2 R5-1		SHS SHS
EXIT 17 RAMP D MM. 0.290 RT	MOUNTED BACK TO BACK	1 1	36 36	36 36	4.50 9.00						2					X		X															RI-2 R5-1		SHS SHS
					SF 64.00	SF	EA.	SF				FT	FT	FT	FT	FT 90	FT		EA	LB	LB	LB		LB	LB	LB	LB	EA.	EA.						
															FT 90					LB		EA.		LB				EA.	EA.						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

INTERCHANGE 17 TRAFFIC SIGN SUMMARY SHEET 4

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSSI7-4.i

PLOT DATE: 8/21/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 130 OF 221