STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REMOVED REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
EXIT 17 US ROUTE 2 MM. 1.954 LT	← 89 SOUTH Winooski Burlington	1	198	126		173.25					2																	2		1000	8X21		FUSE PLATE BOLT TENSION = 28.4 KIPS	43	
EXIT 17 US ROUTE 2 MM. 1.955 RT	JCT	1	21	15	2.19						1					X		X															M2-1 BLACK ON WHITE		SHS
	7	1	24	24	4.00						1																						MI-4		SHS
EXIT 17 US ROUTE 2 MM. 1.955 LT	LEFT LANE MUST TURN LEFT	1	30	30	6.25						1					X		X															R3-7L		SHS
EXIT 17 US ROUTE 2 MM. 1.970 LT	ONLY	1	30	30	6.25						1					X		X															VR-92IL		E-145A
EXIT 17 US ROUTE 2 MM. 1.970 RT		1	36	36	9.00						2						X	X															WII-1		SHS
	SHARE THE ROAD	1	18	24	3.00																												WI6-1		SHS
	0020 0405 0197	1	6	10	0.42																												VD-700		E-138
					SF 31.11	SF 173.25	EA.	SF				FT	FT	FT	FT	FT 45	FT 30		EA	LB	LB	LB		LB	LB	LB	LB	EA. 2	EA.	LB 1000					
												FT			FT 75					LB			EA.	LB										

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

INTERCHANGE 17 TRAFFIC SIGN SUMMARY SHEET 9

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSSI7-9.i

PLOT DATE: 8/21/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 135 OF 221