STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
EXIT 18 RAMP C MM. 0.000 RT	18C 0.000 106.834	1	6	8	0.33						1				X			X																VD-700M PLACE PLAQUE AT PROPER MAINLINE STATION	47	
EXIT 18 RAMP C MM. 0.270 RT	MOUNTED BACK TO BACK WRONG WAY / ← MILTON 4	1 1					1 1				2													2	X											E-123
	← FAIRFAX 6	1					1																													E-123
	← GEORGIA CTR 2	1					1																													E-123
	← GAS /DIESEL 24 HRS	1	72	10	5.00																												VD-502GD	49	
	← CAMPING	1	72	10	5.00																												VD-502C	49	
EXIT 18 RAMP C MM. 0.225 LT	STOP / DO NOT ENTER MOUNTED BACK TO BACK	1 1	30 30	30 30	6.25 6.25						2				X			X																RI-1 R5-1		SHS SHS
	ONE WAY / ONE WAY MOUNTED BACK TO BACK	1 1	36 36	12 12	3.00 3.00																												R6-1L R6-1R		SHS SHS
EXIT 18 RAMP C MM. 0.225 RT	STOP / DO NOT ENTER MOUNTED BACK TO BACK	1 1	30 30	30 30	6.25 6.25						2				X			X																R1-1 R5-1		SHS SHS
	ONE WAY / ONE WAY MOUNTED BACK TO BACK	1 1	36 36	12 12	3.00 3.00																												R6-1L R6-1R		SHS SHS
					SF 47.33	SF	EA. 4	SF			FT	FT	FT	FT 8	FT 60	FT 68		EA	LB	LB	LB	EA. 2	LB 228	LB	LB	LB	EA.	EA.						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

INTERCHANGE 18 TRAFFIC SIGN SUMMARY SHEET 2

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSSI8-2.i

PLOT DATE: 8/21/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 142 OF 221