STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGNS REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
EXIT 18 US ROUTE 7 MM. 1.610 RT	GEORGIA CTR. 2	1	72	12	6.00						2					X		X															D2-1		E-123
	ST. ALBANS 9	1	72	12	6.00																												D2-1		E-123
EXIT 18 US ROUTE 7 MM. 1.610 LT	↑ MILTON 4	1	72	12	6.00						2					X		X															D1-1A		E-123
	↑ FAIRFAX 6	1	72	12	6.00																												D1-1A		E-123
	← BURLINGTON 20	1	72	12	6.00																												D1-1A		E-123
EXIT 18 US ROUTE 7 MM. 1.625 LT	ONLY	1	24	30	5.00						1					X		X															VR-921 (LEFT ARROW)		E-145A
					SF 35.00	SF	EA.	SF				FT	FT	FT	FT	FT 75	FT		EA	LB	LB	LB		LB	LB	LB	LB								
												FT			FT 75					LB			EA.	LB				EA.	EA.						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

INTERCHANGE 18 TRAFFIC SIGN SUMMARY SHEET 8

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSS18-11.1

PLOT DATE: 8/21/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 148 OF 221