STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 / 1.88	2.0 / 2.42	2.5 / 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 / 1.3	4.0 / 1.7	4.0 MOD / 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 / 7.6	3.5 / 9.0	4.0 / 10.8	5.0 / 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																										
EXIT 19 RAMP A MM. 0.000 RT	19A 0.000	1	6	8	0.33						1				X			X																VD-700M	47	
EXIT 19 RAMP A MM. 0.140 LT		1	24	30	5.00						1					X		X															WI-8R FLUORESCENT YELLOW SHEETING (TYPE IX)		SHS
EXIT 19 RAMP A MM. 0.150 RT	TURN SIGNAL REQUIRED BEFORE CHANGING LANES	1	36	36	9.00						2						X	X															VR-002		E-142
	PROHIBITED PEDESTRIANS HITCHHIKERS STOPPING FOR HITCHHIKERS ANIMALS BICYCLES FARM MACHINERY SNOW VEHICLES	1	36	36	9.00																											VR-046		E-142
EXIT 19 RAMP A MM. 0.156 LT		1	24	30	5.00						1					X		X															WI-8R FLUORESCENT YELLOW SHEETING (TYPE IX)		SHS
EXIT 19 RAMP A MM. 0.170 LT		1	24	30	5.00						1					X		X															WI-8R FLUORESCENT YELLOW SHEETING (TYPE IX)		SHS
EXIT 19 RAMP A MM. 0.185 LT		1	24	30	5.00						1					X		X															WI-8R FLUORESCENT YELLOW SHEETING (TYPE IX)		SHS
EXIT 19 RAMP A MM. 0.205 RT		1	36	36	9.00						2					X		X															R3-2		SHS
					SF 47.33	SF	EA.	SF				FT	FT	FT	FT 8	FT 90	FT 30		EA	LB	LB	LB		LB	LB	LB	LB	EA.	EA.						
												FT			FT 128					LB			EA.	LB				EA.	EA.						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

INTERCHANGE 19 TRAFFIC SIGN SUMMARY SHEET 1

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSSI9-1.1

PLOT DATE: 8/21/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 154 OF 221