STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
EXIT 19 RAMP D MM. 0.301RT	FOOD 2 / WRONG WAY MOUNTED BACK TO BACK	1	72	10	5.00		1				2												2	X									VD-502F	49	
	GAS/DIESEL 24 HRS MOUNTED BACK TO BACK	1	72	10	5.00		1																										VD-502GD	49	
	LODGING	1	72	10	5.00																												VD-502L	49	
	HOSPITAL 1	1	72	10	5.00																												VD-502H	49	
	STATE POLICE 1	1	72	10	5.00																												VD-502M	49	
EXIT 19 RAMP D MM. 0.350 RT	YIELD / DO NOT ENTER MOUNTED BACK TO BACK	1 1	48 36	48 36	8.00 9.00						2					X		X															RI-2 R5-1		SHS SHS
EXIT 19 RAMP D MM. 0.357 RT	ONLY	1	30	30	6.25						1					X		X															VR-922L		E-145A
EXIT 19 ST ALBANS HIGHWAY MM. 0.765 CTR		1	24	30	5.00						1					X		X															R4-7		SHS
	MOUNTED BACK TO BACK	1 1	18 18	18 18	2.25 2.25																												OMI-1 OMI-1		SHS SHS
					SF 57.75	SF	EA.	SF				FT	FT	FT	FT	FT 60	FT		EA	LB	LB	LB		LB 228	LB	LB	LB								
															FT					LB			EA. 2					EA.	EA.						
																FT 60								LB 228											

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

INTERCHANGE 19 TRAFFIC SIGN SUMMARY SHEET 4

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSS19-4.i

PLOT DATE: 8/21/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 157 OF 221