STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
EXIT 22 RAMP B MM. 0.040 LT		1	24	30	5.00						1					X		X															WI-8R FLUORESCENT YELLOW SHEETING (TYPE IX)		SHS
EXIT 22 RAMP B MM. 0.060 LT		1	24	30	5.00						1					X		X															WI-8R FLUORESCENT YELLOW SHEETING (TYPE IX)		SHS
EXIT 22 RAMP B MM. 0.080 LT		1	24	30	5.00						1					X		X															WI-8R FLUORESCENT YELLOW SHEETING (TYPE IX)		SHS
EXIT 22 RAMP B MM. 0.090 RT		1	36	36	9.00						2					X		X															R3-2		SHS
EXIT 22 RAMP B MM. 0.097 RT		1	6	8	0.33						1					X		X															VD-700M	47	
EXIT 22 RAMP C MM. 0.000 RT		1	6	8	0.33						1					X		X															VD-700M	47	
EXIT 22 RAMP C MM. 0.010 LT		1	24	30	5.00						1					X		X															R4-7		SHS
	MOUNTED BACK TO BACK	1 1	18 18	18 18	2.25 2.25																												OMI-1 OMI-1		SHS SHS
EXIT 22 RAMP C MM. 0.017 RT		1	24	12	2.00						2					X		X															M3-3 WHITE ON BLUE		SHS
		1	24	24	4.00																												MI-1		SHS
					SF 40.16	SF	EA.	SF			FT	FT	FT	FT 16	FT 120	FT 136		EA	LB	LB	LB	EA.	LB	LB	LB	LB	EA.	EA.							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

INTERCHANGE 22 TRAFFIC SIGN SUMMARY SHEET 3

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSS22-3.i

PLOT DATE: 8/21/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 188 OF 221