STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
EXIT 22 US ROUTE 7 MM. 6.080 RT	END	1	24	12	2.00						1					X		X																M4-6 BLACK ON WHITE		SHS
	7	1	24	24	4.00																												MI-4		SHS
EXIT 22 US ROUTE 7 MM. 6.090 RT		1	24	30	5.00						1					X		X																WI-8R FLUORESCENT YELLOW SHEETING (TYPE IX)		SHS
EXIT 22 US ROUTE 7 MM. 6.110 RT		1	24	30	5.00						1					X		X																WI-8R FLUORESCENT YELLOW SHEETING (TYPE IX)		SHS
EXIT 22 US ROUTE 7 MM. 6.125 RT		1	24	30	5.00						1					X		X																WI-8R FLUORESCENT YELLOW SHEETING (TYPE IX)		SHS
EXIT 22 US ROUTE 7 MM. 6.140 RT		1	24	30	5.00						1					X		X																WI-8R FLUORESCENT YELLOW SHEETING (TYPE IX)		SHS
EXIT 22 US ROUTE 7 MM. 6.155 RT	SWANTON 7	1	72	12	6.00						2					X		X																DI-1A		E-123
	ST. ALBANS 14	1	72	12	6.00																													DI-1A		E-123
EXIT 22 US ROUTE 7 MM. 6.170 LT	THROUGH WAY BEGINS HERE / THROUGH WAY ENDS HERE (MOUNTED BACK TO BACK)	1 1	24 24	24 24	4.00 4.00						1					X		X																VR-041 VR-040		E-141 E-141
					SF 46.00	SF	EA.	SF				FT	FT	FT	FT	FT 120	FT 120		EA	LB	LB	LB	EA.	LB	LB	LB	LB	EA.	EA.						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

INTERCHANGE 22 TRAFFIC SIGN SUMMARY SHEET 10

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSS22-10.i

PLOT DATE: 8/21/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 195 OF 221