STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
NORTHBOUND REST AREA HANDICAP RAMP	RESERVED PARKING	1	12	18	1.50						1					X		X															R7-8M	46	
NORTHBOUND REST AREA CAR/ TRUCK LOOP	$500 FINE FOR THROWING TRASH ON HIGHWAYS AND STREAMS	1	24	30	5.00						1					X		X															VR-023B		E-144
NORTHBOUND REST AREA CAR/ TRUCK LOOP		1	24	24	4.00						1					X		X															VR-654		E-143
NORTHBOUND REST AREA CAR/ TRUCK LOOP	SAFETY BELTS REQUIRED	1	30	36	7.50						1					X		X															VR-601	47	
NORTHBOUND REST AREA CAR/ TRUCK LOOP		1	36	36	9.00						2					X		X															R3-2		SHS
NORTHBOUND REST AREA CAR/ TRUCK LOOP	NR 110 0266 110.456	1	6	8	0.33						1				X			X															VR-700M	47	
NORTHBOUND REST AREA CAR/ TRUCK LOOP	WALK DOGS HERE	1	12	18	1.50						1					X		X															VR-541		E-144
	ALL DOGS MUST BE ON LEASH	1	24	24	4.00																												VR-648		E-144
SHEET 201					45.50											150		10																	
SHEET 202					40.25											135		9																	
SHEET 203					32.83										8	105		8																	
												FT	FT	FT	FT 8	FT 390	FT		EA	LB	LB	LB		LB	LB	LB	LB								
					SF 118.58	SF	EA.	SF				FT			FT 398					LB			EA.	LB				EA.	EA.						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

NORTHBOUND REST AREA TRAFFIC SIGN SUMMARY SHEET 3

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSSNBRA-3.i

PLOT DATE: 8/21/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 203 OF 221