STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																										
SOUTHBOUND REST AREA TRUCK LOOP		1	24	24	4.00						1					X		X																	R8-3A		SHS
SOUTHBOUND REST AREA TRUCK LOOP		1	12	18	1.50						1					X		X																	VR-541		E-144
SOUTHBOUND WEIGH STATION TRUCK LOOP		1	36	24	6.00						2					X		X																	R5-1A		SHS
SOUTHBOUND REST AREA TRUCK LOOP	MOUNTED BACK TO BACK	1 1	36 36	36 24	4.50 6.00						2					X		X																	R1-2 R5-1A		SHS SHS
SOUTHBOUND REST AREA CAR/ TRUCK LOOP		1	36	12	3.00						2					X		X																	R6-1R		SHS
SOUTHBOUND REST AREA CAR/ TRUCK LOOP		1	30	36	7.50						1					X		X																	VR-601	47	
SOUTHBOUND REST AREA CAR/ TRUCK LOOP		1	36	36	9.00						2					X		X																	R3-2		SHS
SOUTHBOUND REST AREA CAR/ TRUCK LOOP		1	36	30	7.50						2					X		X																	VD-243D REMOVE SIGN FROM POLE AND INSTALL MIN. OF 10 FEET FROM POLE.	46	
SHEET 206 SHEET 207 SHEET 208					52.25 27.50 49.00											150 135 195		10 9 13																	ALL SIGNS SHOWN ARE TO REPLACE EXISTING SIGNS AT THIER EXISTING LOCATIONS, UNLESS OTHERWISE DIRECTED BY THE ENGINEER.		
					SF 128.75	SF	EA.	SF				FT	FT	FT	FT	FT 480	FT		EA	LB	LB	LB	EA.	LB	LB	LB	LB	EA.	EA.						
																480																				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

SOUTHBOUND REST AREA TRAFFIC SIGN SUMMARY SHEET 3

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSSSBRA-3.1

PLOT DATE: 8/21/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 208 OF 221