STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 19

MILE MARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	SQUARE STEEL (in) lb/ft 2.0 2.42	SQUARE STEEL (in) lb/ft 2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) lb/ft 3.0 1.3	TUBULAR ALUMINUM DIA (in) lb/ft 4.0 1.7	TUBULAR ALUMINUM DIA (in) lb/ft 4.0Mod 1.7	TUBULAR STEEL DIA (in) FND-ATION	TUBULAR STEEL DIA (in) lb/ft 3.0 7.6	TUBULAR STEEL DIA (in) lb/ft 3.5 9.0	TUBULAR STEEL DIA (in) lb/ft 4.0 10.8	TUBULAR STEEL DIA (in) lb/ft 5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
64.520 SB	EXIT 10	1	96	30	20.00																													152	
	Waterbury Stowe	1	168	138		161.00																												136	
	NEXT EXIT 5 MILES	1	162	24		27.00					2																	2		857	W8X21		Fuse-Plate Bolt Tension 31.2 kips	152	
64.750 SB	Waitsfield Warren EXIT 10	1	138	84		80.50					2																	2		492	W6X12		Fuse-Plate Bolt Tension 12 kips	143	
64.838 SB MED		1	36	36	9.00						2					X		2															R3-4		
64.970 SB	EXIT 10	1	96	30	20.00																													152	
	Waterbury Stowe	1	168	144		168.00					2																	2		983	W8X21		Fuse-Plate Bolt Tension 29.5 kips	136	
65.000 SB	65	1	12	36	3.00						1					X		1															D10-2		E-139
65.280 SB		1	12	36	3.00						1				X			1															OM-3R		
65.280 SB MED		1	12	36	3.00						1				X			1															OM-3L		
65.385 SB		1	12	36	3.00						1				X			1															OM-3R		
65.385 SB MED		1	12	36	3.00						1				X			1															OM-3L		
65.500 SB		1	48	48	16.00						2											2	X										W8-13		
66.000 SB	66	1	12	36	3.00						1					X		1															D10-2		E-139
66.160 SB		1	48	48	16.00																												VW-001	151	
	NEXT 2 MILES	1	30	24	5.00						2										X													151	
66.650 SB		1	12	36	3.00						1				X			1															OM-3R		
												FT	FT	FT	FT 63.0	FT 54.0	FT		EA.	LB	LB 71.6	LB		LB 205.2	LB	LB	LB							
	SUBTOTALS SHEET 19				SF 107.00	SF 436.50	EA.	SF				FT			FT 117.0					LB 71.6			EA. 2	LB 205.2				EA. 6	EA.	LB 2332					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: WATERBURY - WINOOSKI
PROJECT NUMBER: IM G SIGN(18)

FILE NAME:	090124 tss main SB.xls	PLOT DATE:	10/27/2009
PROJECT LEADER:	CRB	DRAWN BY:	JH
DESIGNED BY:	BDB	CHECKED BY:	DAM
TRAFFIC SIGN SUMMARY SHEET # 19		SHEET 77	OF 174