STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 23

MILE MARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																					REMARKS	SIGN DETAIL	
												FLANGED CHANNEL			SQUARE STEEL (in)					TUBULAR ALUMINUM DIA (in)			TUBULAR STEEL DIA (in)					W-SHAPE STEEL						
		E A	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	lb/ft			1.75	2.0	2.5	ANCHOR	SLEEVE	3.0	4.0	4.0Mod	FND-ATION	3.0	3.5	4.0	5.0	FTG. SIZE		WEIGHT	POST SIZE	SIGN FRAME		DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												1.12	2.0	3.0	1.88	2.42	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6	24"	30"						
77.000 SB		1	12	36	3.00						1					X		1															D10-2		E-139
77.050 SB	KEEP RIGHT EXCEPT TO PASS	1	48	60	20.00						2										X												VR-132	151	
77.050 SB MED	KEEP RIGHT EXCEPT TO PASS	1	48	60	20.00						2												2	X									VR-132	151	
77.099 SB		1	12	36	3.00						1				X			1															OM-3R		
77.099 SB MED		1	12	36	3.00						1				X			1															OM-3L		
77.225 SB	SCHOOL BUS BEFORE ROUTE	1	48	48	16.00						2									X													W8-13		
77.340 SB	Waterbury 14 Montpelier 25	1	114	36		28.50					2												2	X										143	
77.565 SB	MOOSE	1	48	48	16.00																												VW-001	151	
	NEXT 15 MILES	1	30	24	5.00						2										X													151	
77.700 SB	SPEED LIMIT 65	1	48	60	20.00																												R2-1		
	MINIMUM 40	1	48	48	16.00						2												2		X								VR-141		E-142
77.800 SB		1	48	48	16.00																												VW-397	151	
	GROOVED SHOULDER	1	24	18	3.00						2										X												VP-396	151	
77.895 SB	SOUTH	1	30	15	3.13																												M3-3 WHITE ON BLUE		
	INTERSTATE 89	1	36	36	9.00																												M1-1		
	PROTECTED CROSSING	1	36	36	9.00						1												1	X									M1-10		
77.970 SB	EMERGENCY STOPPING ONLY	1	48	36	12.00						2												2	X									R8-7		
												FT	FT	FT	FT 25.2	FT 10.5	FT		EA.	LB 49.6	LB 213.1	LB		LB 694.7	LB 324.9	LB	LB							
		SUBTOTALS SHEET 23			SF 174.13	SF 28.50	EA.	SF				FT			FT 35.7					LB 262.7			EA. 9	LB 1019.6				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: WATERBURY - WINOOSKI
PROJECT NUMBER: IM G SIGN(18)

FILE NAME:	090124 tss main SB.xls	PLOT DATE:	10/27/2009
PROJECT LEADER:	CRB	DRAWN BY:	JH
DESIGNED BY:	BDB	CHECKED BY:	DAM
TRAFFIC SIGN SUMMARY SHEET # 23		SHEET 81	OF 174