STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 37

MILE MARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) lb/ft 3.0 1.3	4.0 1.7	4.0Mod 1.7	TUBULAR STEEL DIA (in) FND-ATION	3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
0.125 RAMP F RT	GAS/DIESEL GAS/DIESEL 24 HOURS	1 1	72 72	10 10	5.00 5.00																												VD-502G VD-502G		
	FOOD 1 LODGING 1	1 1	72 72	10 10	5.00 5.00																												VD-502F VD-502L		
	INFORMATION CAMPING 5	1 1	72 72	10 10	5.00 5.00																												VD-502I VD-502C		
	8 RV CAMPING	1	72	10	5.00						2										X												VD-502C		
0.155 RAMP F LT		1	18	18	2.25						1				X			1															OM1-1		
0.160 RAMP F LT	NORTH SOUTH TO	1 1 1	24 24 24	12 12 12	2.00 2.00 2.00																												M3-1 GREEN ON WHITE M3-3 GREEN ON WHITE M4-5 BLACK ON WHITE		
	VERMONT 100 VERMONT 100 2	1 1 1	30 30 24	24 24 24	5.00 5.00 4.00																												M1-5 M1-5 M1-4		E-136B E-136B
		1 1 1	21 21 21	15 15 15	2.19 2.19 2.19																											#3B	M6-1 GREEN ON WHITE M6-2 GREEN ON WHITE M6-2 BLACK ON WHITE		
	WRONG WAY	1	42	30	8.75						2												2	X									R5-1a BACK TO BACK		
0.160 RAMP F LT	WRONG WAY	1	42	30	8.75						2					X		2															R5-1a		
0.170 RAMP F RT		1	36	36	9.00						2					X		2															W4-6		
0.195 RAMP F RT	DO NOT ENTER	1 1	30 36	30 36	6.25 9.00						1					X		1															R3-2 BACK TO BACK R5-1		
INT #10 0.030 RAMP H RT		1	36	36	9.00																												VR-046		E-142
	TURN SIGNAL REQUIRED BEFORE CHANGING LANES	1	36	36	9.00						2												2	X									VR-002		E-142
0.140 RAMP H RT		1	30	30	6.25						1					X		1															R3-2		
												FT	FT	FT	FT 9.5	FT 89.4	FT		EA.	LB	LB 69.6	LB		LB 369.5	LB	LB	LB								
		SUBTOTALS SHEET 37			SF 129.82	SF	EA.	SF				FT			FT 98.9					LB 69.6			EA. 4	LB 369.5				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: WATERBURY - WINOOSKI
PROJECT NUMBER: IMG SIGN(18)

FILE NAME:	090124 tss int10.xls	PLOT DATE:	10/27/2009
PROJECT LEADER:	CRB	DRAWN BY:	JH
DESIGNED BY:	BDB	CHECKED BY:	DAM
TRAFFIC SIGN SUMMARY SHEET # 37		SHEET 95	OF 174