STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 38

MILE MARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS E A	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) 3.0 lb/ft 1.3	4.0 1.7	4.0Mod 1.7	TUBULAR STEEL DIA (in) FND-ATION	3.0 lb/ft 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN	FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
INT #10 0.092 VT 100 RT	JCT	1	21	15	2.19																													M2-1 WHITE ON BLUE		
	INTERSTATE 89	1	24	24	4.00						1					X		1																M1-1		
0.105 VT 100 LT	← WATERBURY ← WAITSFIELD 11	1	72	12	6.00																													D1-1		E-123
		1	72	12	6.00																													D1-1a		E-123
	← WARREN 18 BOLTON 7 →	1	72	12	6.00																													D1-1a		E-123
		1	72	12	6.00																													D1-1a		E-123
	RICHMOND 15 →	1	72	12	6.00																													D1-1a BACK TO BACK W/ ABOVE		E-123
	EAST SOUTH WEST	1	24	12	2.00																													M3-2 BLACK ON WHITE		
		1	24	12	2.00																													M3-3 GREEN ON WHITE		
		1	24	12	2.00																													M3-4 BLACK ON WHITE		
	2 VERMONT 100 2	1	24	24	4.00																													M1-4		
		1	30	24	5.00																													M1-5		E-136B
		1	24	24	4.00																													M1-4		
		1	21	15	2.19																													M6-1 BLACK ON WHITE		
		1	21	15	2.19						2												2			X						#3B	M6-1 GREEN ON WHITE		
		1	21	15	2.19																													M6-1 BLACK ON WHITE		
0.120 VT 100 RT	↑ RICHMOND 16 ↑ BURLINGTON 26	1	72	12	6.00																													D1-1a		E-123
		1	72	12	6.00																													D1-1a		E-123
	MIDDLESEX 6 ↗ MONTPELIER 12 ↗	1	72	12	6.00																													D1-1a		E-123
		1	72	12	6.00						2											X												D1-1a		E-123
0.135 VT 100 LT	13-10	1	36	36	9.00																													W12-2		
		1	21	15	2.19						2					X		2																M5-1 WHITE ON BLUE		
0.155 VT 100 RT	NORTH NORTH SOUTH	1	24	12	2.00																													M3-1 GREEN ON WHITE		
		1	24	12	2.00																													M3-1 WHITE ON BLUE		
		1	24	12	2.00																													M3-3 WHITE ON BLUE		
	VERMONT 100 INTERSTATE 89 INTERSTATE 89	1	30	24	5.00																													M1-5		E-136B
		1	24	24	4.00																													M1-1		
		1	24	24	4.00																													M1-1		
		1	21	15	2.19																													M6-3 GREEN ON WHITE		
		1	21	15	2.19						2											X										#3A	M6-3 WHITE ON BLUE		
		1	21	15	2.19																													M6-2 WHITE ON BLUE		
0.165 VT 100 LT		1	36	36	9.00						2					X		2																W3-1a		
0.165 VT 100 CL		1	36	36	9.00						2					X		2	2															W3-1a		
												FT	FT	FT	FT	FT 112.6	FT	EA. 2		LB	LB 132.7	LB		LB	LB	LB 386.7	LB								
	SUBTOTALS SHEET 38				SF 140.52	SF	EA.	SF				FT			FT	112.6		LB		132.7			EA. 2	LB		386.7		EA.	EA.	LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: WATERBURY - WINOOSKI
PROJECT NUMBER: IMG SIGN(18)

FILE NAME: 090124 tss int10.xls
PROJECT LEADER: CRB
DESIGNED BY: BDB
TRAFFIC SIGN SUMMARY SHEET # 38

PLOT DATE: 10/27/2009
DRAWN BY: JH
CHECKED BY: DAM