STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 49

MILE MARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) lb/ft 3.0 1.3	4.0 1.7	4.0Mod 1.7	TUBULAR STEEL DIA (in) FND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN	FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
1.290 US 2 RT	RICHMOND 2 BOLTON 8	1	72	12	6.00						2					X		2																D2-1		E-123
		1	72	12	6.00																													D2-1		E-123
1.320 US 2 LT	JCT	1	21	15	2.19																													M2-1 WHITE ON BLUE		
	INTERSTATE 89	1	24	24	4.00						1					X		1																M1-1		
INT#12 0.075 RAMP A RT		1	36	36	9.00						2					X		2																W3-3		
0.110 RAMP A RT	SOUTH NORTH	1	24	12	2.00																													M3-3 GREEN ON WHITE		
		1	24	12	2.00																													M3-1 GREEN ON WHITE		
	VERMONT 2A VERMONT 2A	1	24	24	4.00																													M1-5		E-136B
		1	24	24	4.00																													M1-5		E-136B
		1	21	15	2.19																												#2	M6-1 GREEN ON WHITE		
		1	21	15	2.19																													M6-1 GREEN ON WHITE		
	TO TO	1	24	12	2.00																													M4-5 GREEN ON WHITE		
		1	24	12	2.00																													M4-5 BLACK ON WHITE		
	VERMONT 116 2	1	30	24	5.00																													M1-5		E-136B
		1	24	24	4.00																													M1-4		
		1	21	15	2.19						2												2	X									#2A	M6-1 GREEN ON WHITE		
		1	21	15	2.19																													M6-1 BLACK ON WHITE		
0.145 RAMP A RT	HINESBURG 8 BRISTOL 25	1	72	12	6.00																													D1-1a		E-123
		1	72	12	6.00																													D1-1a		E-123
	AIRPORT 3 WILLISTON 3	1	72	12	6.00																													D1-1a		E-123
		1	72	12	6.00																													D1-1a		E-123
	ESSEX JCT 4	1	72	12	6.00						2												2	X										D1-1a		E-123
0.180 RAMP A LT	WRONG WAY	1	36	24	6.00																													R5-1a		
		1	24	24	4.00						2					X		2																R9-4a		
												FT	FT	FT	FT	FT 106.8	FT	EA.		LB	LB	LB		LB 435.6	LB	LB	LB								
	SUBTOTALS SHEET 49		SF 100.95	SF	EA.	SF						FT			FT 106.8					LB			EA. 4		LB 435.6			EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: WATERBURY - WINOOSKI
PROJECT NUMBER: IMG SIGN(18)

FILE NAME: 090124 tss int11 12.xls
PROJECT LEADER: CRB
DESIGNED BY: BDB
TRAFFIC SIGN SUMMARY SHEET # 49

PLOT DATE: 10/27/2009
DRAWN BY: SRB
CHECKED BY: DAM
SHEET 107 OF 174