STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 61

MILE MARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	SQUARE STEEL (in) lb/ft 2.0 2.42	SQUARE STEEL (in) lb/ft 2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) lb/ft 3.0 1.3	TUBULAR ALUMINUM DIA (in) lb/ft 4.0 1.7	TUBULAR ALUMINUM DIA (in) lb/ft 4.0Mod 1.7	FND-ATION	TUBULAR STEEL DIA (in) lb/ft 3.0 7.6	TUBULAR STEEL DIA (in) lb/ft 3.5 9.0	TUBULAR STEEL DIA (in) lb/ft 4.0 10.8	TUBULAR STEEL DIA (in) lb/ft 5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
0.700 EB		1	48	48	16.00																													VW-397	151	
		1	24	18	3.00						2											2	X										VP-396	151	
0.800 EB		1	48	60	20.00																												R2-1		
		1	48	48	16.00						2											2		X									VR-141		E-142
0.810 EB O/H		1 1 1	168 156 174	150 90 150		175.00 97.50 181.25																											OVERHEAD TRAFFIC SIGN SUPPORT, MULTI-SUPPORT	148 148 148	
1.000 EB		1	12	24	2.00						1				X			1															D10-1		E-139
1.220 EB		1	48	60	20.00						2											2	X										W13-3 FLUORESCENT-YELLOW SHEETING		
1.220 EB MED		1	48	60	20.00						2										X												W13-3 FLUORESCENT-YELLOW SHEETING		
1.288 EB O/H		1 1 1	168 162 216	156 96 132		182.00 108.00 198.00																											OVERHEAD TRAFFIC SIGN SUPPORT, MULTI-SUPPORT	149 149 149	
1.320 EB		1	18	18	2.25						1				X			1															OM1-1		
1.438 EB O/H		1 1	216 162	120 96		180.00 108.00																											BRIDGE MOUNTED	149 149	
INT. I-189 / US 7 0.027 RAMP N-E LT		1	18	18	2.25						1				X			1															OM1-1		
0.030 RAMP N-E LT		1	24	12	2.00																												M3-2 WHITE ON BLUE		
		1	30	24	5.00																												M1-1		
		1	21	15	2.19						1					X		1															M6-2 WHITE ON BLUE		
												FT	FT	FT	FT 28.5	FT 14.5	FT		EA.	LB	LB 68.2	LB		LB 425.6	LB 315.0	LB	LB								
		SUBTOTALS SHEET 61			SF 110.69	SF 1229.75	EA.	SF				FT			FT 43.0					LB 68.2			EA. 6	LB 740.6				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: WATERBURY - WINOOSKI
PROJECT NUMBER: IMG SIGN(18)

FILE NAME: 090124 tss int13 15.xls
PROJECT LEADER: CRB
DESIGNED BY: BDB
TRAFFIC SIGN SUMMARY SHEET # 61

PLOT DATE: 10/27/2009
DRAWN BY: SRB
CHECKED BY: DAM